

4 060006

X 7-12

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 009-23,453-00-00
NE SE NW, SEC. 34, T 16 S, R 12 W
3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656
Operator: Davis Petroleum
Name & Address Rt. 1 Box 183B
Great Bend, KS 67530

Lease Name Redetzke Well # 1
County Barton 108.68
Well Total Depth 3344 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well XXXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Great Bend, KS

Company to plug at: Hour: 9:30AM Day: 12 Month: July Year: 1989

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316/793-9711

were: Sand bottom of well to 3300' and spot 5 sxs. cement
Order 200 sxs. 60/40 pos. 6% gel and 500# hulls

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXX Part None

Operations Completed: Hour: 10:30AM Day: 12 Month: July Year: 1989

ACTUAL PLUGGING REPORT 8 5/8" set at 429' w/250 sx. 5 1/2" set at 3338' w/100 sxs.

7' of open hole. Sanded back to 3300' and spotted 5 sxs. cement w/ dump bailer.
Shot and recovered 2037' of 5 1/2" casing. Pumped into 8 5/8" 200 sxs. 60/40 pos 6 % gel
w/ 500# hulls. Max pressure 800#. Shut-in pressure 750#

Remarks: R-1 Titan Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 7-20-89

INV. NO. 25379

Signed Herb Deines (TECHNICIAN)