

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN - 6 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas

Lease Name Feltes Well No. # 3

Location NE SW NE Sec. 34 Twp. 16 Rge. 12 (E) (W)

County Barton Total Depth 3338

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Company

Address: Box 313, Russell, Kansas License No.

Operation Completed: Hour 10:30 AM Day 31 Month 5 Year 1966

The Above well was plugged as follows:

8 5/8" 200' Cwc. 4 1/2" 3336'. Plug @ 3114'. Perf. 3057'.

Displaced 15 sax cement @ 3050' with Halliburton Cementing Company's pump truck.

Pulled pipe. Mudded hole to 200', set rock bridge, displaced 5 sax cement. Let

set over night, bailed hole dry & displaced 3 yds. ready-mix cement, cementing

to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: John L. Ruess
Well Plugging Supervisor

DATE 6/6/66

INV. NO. 3342-W