

15-009-19392-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

OCT 19 1964

CONSERVATION DIVISION
Wichita, Kansas

10-19-1964

Operator's Full Name Sam P. Wallingford, Inc.

Complete Address: 304 Colo. Derby Bldg., Wichita, Kansas

Lease Name Jenisch Well No. # 1

Location SE SW SE Sec. 34 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3378

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Mayfield & Smith Drlg., Inc.

Address: 928 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour 1:30 PM Day 14 Month 10 Year 1964

The Above well was plugged as follows:

8 5/8" 200' Cwc.

Filled hole with heavy mud to 400'; set plug; displaced 20 sax cement
thru drill pipe. Mud to 190'; set plug with 1/4 sax hulls; displaced 20
sax cement thru drill pipe. Mud to 40'; 1/2 sax hulls; plug & displaced
10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/19/64

INV. NO. 9994-u

Signed: [Signature]
Well Plugging Supervisor