

15-009-19398-00-00

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 39-19

LOCATION NE-NE-NE

SEC. 36 TWP. 16 RGE. 17W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease J. B. Hoffman "B"

Operator Russell Iron & Metal Co. Address Box 661 Russell Kans.

Field _____ County Barton

Total Depth 3375 Feet.

Plugging Contractor R & S. Pipe Pulling Co

Plugging Contractor's License No. #1.

Address Box 192 Ellinwood Kans.

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1954
6-19-54
CONSERVATION DIVISION
Wichita, Kansas

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4" @ 760' No Cem. Oil string 5 1/2" O.P.
Set 3369 w/ 75 st Cem. Sanded hole to 3350'
and dumped 5 st Cem shot off and pulled
5 1/2" casing. Freed 10" casing. Set bridge at
240' thru 10" casing after hole was mudded
and run 40 st Cem. Laid down Pipe. Mudded
hole to 20' set rock bridge and 10 st of
Cem to base of cellar.

Warren H. Garner
District Conservation Agent

Date June 15, 1954

PLUGGING
FILE SEC 36 T. 16 R. 17W
BOOK PAGE 39 LINE 19