

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name W. H. Peachee

Complete Address: 1005 Central Bldg., Wichita, Kansas

Lease Name Davis Well No. # 3

Location NW NW NW Sec. 3 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3549'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:45 AM Day 26th Month April Year 1966

The Above well was plugged as follows:

806' of 8 5/8" surface pipe, cemented with 400 sacks. 3549' of 5 1/2" long  
string, cemented with 125 sacks. Plug back T.D. 3425'. Top perforation  
3372'. Bottom of the hole was sanded to 3300', and cemented with 5 sacks,  
through the dump bailer. 2785' of 5 1/2" long string was recovered from the  
hole. Fluid level in the hole was at 300'. Bridge plug was set on fluid at  
300', rock bridge from 300' to 290', and cemented with 25 sacks. Hole was  
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10  
sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audrie Elving  
Well Plugging Supervisor

DATE 4/28/66

INV. NO. 3124-W