

15.185.20041.0000

Form CP-3  
Rev. 6-9-67

KANSAS

**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION

JUL 24 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed July 3, 1967.

Operator's Full Name Sage Drilling Company, Inc. & F. G. Holl

Complete Address 500 Bitting Bldg., Wichita, Kansas 67202

Lease Name Fair Well No. # 1

Location SE SW NE Sec. 14 Twp. 21 Rge. 11 (E) (W)W

County Stafford Total Depth 3460'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Sage Drilling Company, Inc.

Address 500 Bitting Bldg., Wichita, Kansas 67202 License No.     

Operation Completed: Hour 5:00 P.M. Day 21st Month July Year 1967

The above well was plugged as follows:

230' of 8 5/8" surface pipe, cement circulated with 235 sacks. Fluid  
level in the hole was at 170'. 1st cementing plug and 1/4 sack of hulls  
was pushed in fluid to 210', and cemented with 25 sacks, through the  
drill pipe, with cement from 210' to 135'. Hole was filled with drilling  
mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement and  
1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base  
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie E. Elving  
Well Plugging Supervisor

DATE 7/24/67

INV. NO. 6015-W