

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 54-37

LOCATION C 1/4 - SW - SE

SEC. 6 TWP. 21 RGE. 13-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Morrison

Operator Sunray Oil Co. Inc. Address Box #195 - St. Paul - Kans.

Field _____ County Stafford

Total Depth 3620 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 810 ft. Circulated with cement -
3/4" casing set at 3616 ft. - Cemented with 15 sacks of
cement - Plugged back to 3600 ft. with chert - Pumped
5 sacks of cement at 3600 ft. Shot off & pulled the
3/4" casing - Filled hole with sand to 2500 ft. Set Rock
Bridges & 15 sacks of cement at 2500 ft. Sand to 3000
ft. & 10 sacks of cement at the surface -
Fisher Casing & Plugging Co. - Plugging

STATE CORPORATION COMMISSION

FEB 20 1951

CONSERVATION DIVISION
Wichita, Kansas

C. W. Stover
District Conservation Agent

Date 1-17-51

PLUGGING
FILE SEC. 6 T 21 R 13 W
BOOK PAGE 55 LINE 37