

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Woodman-Iannitti Drlg Co

Complete Address Box 308 Great Bend, KS

Lease Name Morrison Well No. 1-SWD

Location W/2 SW/SE Sec. 6 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 2120

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering Inc

Address Box 698 Great Bend, KS License No. 670

Operation Completed: Hour 2:00 PM Day 14 Month 11 Year 1974

The above well was plugged as follows:
810 ft 8 5/8 Surface cemented with 550 sacks. 1824 ft 5 1/2 long string
cemented with 100 sacks. Open hole. Sand to 1800 ft, 5 sacks cement
with bailer. Pulled 1275 ft 5 1/2. Set 10 ft rock bridge at 300 ft.
Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed [Signature]
Well Plugging Supervisor

INVOICED

DATE 11/19/74
INV. NO. 321-W