

f

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 185-01688.0001 (of this well)

Operator's Full Name Joe Brougher

Complete Address Box 1367-Great Bend, Ks. 67530

Lease Name Parish Well No. 2

Location SW SE SW Sec. 6 Twp. 21S Rge. 13 (E) (W) X

County Stafford Total Depth 3626

Abandoned Oil Well Gas Well Input Well X SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Sun Oil Well cementing, Inc.

Address Box 169 Great Bend, Ks. 67530 License No.

Operation Completed: Hour 3 Pm. Day 12 Month 4 Year 1979

The above well was plugged as follows:

246' 8 5/8" casing. 4 1/2" casing set at 3626'. Top perforation at 3456'
Lost tools in hole-Pull 222' 4 1/2" casing. Run impression block to
500'-No fish. Sun mixed and pumped 5 sax hulls-25 sax gel-125 sax 50/50
posmix w/3% gel to top of casing. Shut in w/ 100# pressure.

RECEIVED
STATE CORPORATION COMMISSION

APR 16 1979

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

D. 4-17-79
INV. NO. 9441-w