

15.185.20166.0000

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1974


CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
State Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County, Sec. 14 Twp. 21 Rge. 13 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SE/4
Lease Owner Aspen Drilling Co.
Lease Name Hall Well No. #2
Office Address Box 783 ; Great Bend, Ks. 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed June 1974
Application for plugging approved June 1974
Plugging commenced July 1 1974
Plugging completed July 8 1974
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	251	None
				5 1/2"	3658	2720

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

July 1, 1974 Plugged off bottom. Dumped sand to 3300'. Mixed and dumped 5 sx of cement.
July 8, 1974 Plugged off top. Sun Oil Well Cementing Co mixed and pumped down 8 5/8" surface casing: 3 sx of hulls, 10 sx of gel and 100 sx of cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082 ; Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton
John H. Volosin (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P. O. Box 783, Great Bend, Kansas (Address)

Subscribed and sworn to before me this 16th day of July 1974

My commission expires April 18, 1976
Theora Holleman Notary Public

15.185.20166.0000
 RECEIVED
 STATE CORPORATION COMMISSION
 JUN 27 1974
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLERS LOG

COMPANY: Aspen Drilling Co.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Hall #2
 LOCATION: C SE/4 Sec. 14-T21S-R13W
 Stafford County, Kansas

ELEVATION: 1870 KB
 SURFACE CASING: 6 jts. (251') 8 5/8"
 OIL STRING: 114 jts. (3660') 5 1/2"
 COMMENCED: April 4, 1969
 COMPLETED: April 15, 1969
 ROTARY TOTAL DEPTH: 3660'

<u>FORMATION</u>	<u>DEPTH</u>	
Red Bed & Shale	719	Ran 6 jts. (251') 8 5/8" casing set at 250' w/250 sacks. Cement circulated.
Anhydrite	733	
Shale & Shells	1040	
Shale & Lime	1865	DST #1 3292-3330
Lime & Shale	2585	DST #2 3338-3358
Shale & Lime	2790	DST #3 3389-3416
Lime & Shale	3138	DST #4 3417-3456
Heebner	3144	DST #5 3568-3582
Lime & Shale	3290	DST #6 3586-3598
Lime	3540	DST #7 3592-3614
Conglomerate	3565	DST #8 3610-3619
Arbuckle	3660	
RTD	3660	Ran 114 jts. (3660') 5 1/2" set at 3658' w/160 sacks.

ELECTRIC LOG TOPS

Anhydrite	712
Base Anhydrite	732
Heebner	3137
Brown Lime	3261
Lansing	3278
Base K. C.	3498
Conglomerate	3518
Simpson	3546
Arbuckle	3564
Log TD	3659


AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle, Affiant

Subscribed and sworn to before me this 21st day of May, 1969.



Theora Holleman
 Theora Holleman, Notary Public

My commission expires: April 18, 1972.