


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Flat

Stafford County. Sec. 14 Twp. 21S Rge. (E) 11 (W)  
Location as "NE/CNW%SW%" or footage from lines SE SW NE  
Lease Owner Sage Drilling Co., Inc.-F. G. Holl, et al  
Lease Name FAIR Well No. 1  
Office Address 500 Bitting Building, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 21, 19 67  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced July 21, 19 67  
Plugging completed July 21, 19 67  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Archie Elving)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 3460 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	230'	8-5/8"	7/14/67	-----
	Casing					
RECEIVED STATE CORPORATION COMMISSION JUL 26 1967 CONSERVATION DIVISION						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from Total Depth to 210 Feet;  
Hull Plug, Plug and 25 sacks Cement  
thru the Drill Pipe; Mud to 40 Feet;  
1/2 sack Hulls, Plug bridged with Kelly  
and 10 sacks Cement to Base of Cellar;  
2 sacks in Rat Hole. Job completed at  
5 P.M

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Lawrence F. Gray of Sage Drilling Co (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray  
500 Bitting Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of July, 19 67  
Louise K. Whitted  
Notary Public.

My commission expires November 26, 1970.

DRILLERS LOGFAIR NO. 1

CASING RECORD:	COMPANY:	Sage-Holl, et al	DESCRIPTION:
8-5/8" @ 230' w/235 sax cement	CONTRACTOR:	Sage Drilling Co.	SE SW NE Sec. 14-21S-11W Stafford County, Kansas
TOTAL DEPTH: 3460'	COMMENCED:	July 14, 1967	ELEVATION: 1737KB
	COMPLETED:	July 21, 1967	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	90	
Blue Clay	90	120	
Sand	120	150	
Red Bed	150	231	
Red Bed & Shale	231	430	
Anhydrite	430	450	
Shale	450	745	
Shale & Lime	745	1475	
Shale, Shells & Lime	1475	1694	
Lime & Shale	1694	1895	
Shale & Lime	1895	2760	
Lime & Shale	2760	3010	
Shale & Lime	3010	3125	
Lime	3125	3240	
Lime & Shale	3240	3325	
Lime & Chert	3325	3364	
Shale	3364	3410	
Lime & Shale	3410	3460	D&A

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 26 1967

CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray  
Lawrence F. Gray

Subscribed and sworn to before me this 25th day of July, 1967.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.