


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Stafford County. Sec. 6 Twp. 21S Rge. (E) 13(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE
Lease Owner Westgate-Greenland Oil Company
Lease Name Morrison Well No. 1
Office Address 1022 Union Natl Bk Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed May 9, 1949 19
Application for plugging filed May 9, 1949 (orally) 19
Application for plugging approved May 12, 1949 (written) 19
Plugging commenced May 9, 1949 19
Plugging completed May 9, 1949 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
surface		0	284	8 5/8"	284	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Filled hole with heavy mud from 3650 to 280 feet
Set plug at 280 feet and ran 20 sacks cement
Filled hole 30 feet with heavy mud and ran 10 sacks cement to cellar base.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company Attn G. E. Bitler
Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler, Production Supt. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *G. E. Bitler*


1022 Union National Bank Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of May 19 49

Esther [Signature]
Notary Public.

My commission expires May 25, 1953

22-5133-s 9-48-10M



MAY 26 1949 5-26-1949
STATE CORPORATION COMMISSION
WICHITA, KANSAS

COMPANY: Westgate Greenland Oil Company
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Morrison #1
 LOCATION: NE NE NE Section 6-21S-13W,
 Stafford County, Kansas
 ELEVATION: 1899
 COMMENCED: April 25, 1949
 COMPLETED: May 9, 1949

0	to	145	Sand
145	to	300	Pyritic shale
300	to	760	Red bed & shale
760	to	770	Shale & shells red bed
770	to	790	Harde sand
790	to	1375	Red bed & shale
1375	to	1555	Shale & shells, salt
1555	to	1775	Lime & shale
1775	to	1810	Lime Harde
1810	to	1990	Lime
1990	to	2070	Shale & shells
2070	to	2330	Lime shale
2330	to	2425	Shale & shells
2425	to	2675	Shale
2675	to	2900	Lime & shale
2900	to	2650	Lime
		3650	T.D.

8 5/8" - 24# casing set at 284 feet. Cemented with 250 sacks cement.

Top Arbuckle 3624

Dry and abandoned

Measurements taken from top of derrick floor.

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Morrison #1, Section 6-21S-13W, Stafford County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 18th day of May, 1949.

Dorothy J. Wilson
 Dorothy J. Wilson

My Commission expires November 30, 1950

RECEIVED
 Conservation Div.
 MAY 26 1949
 STATE CORPORATION
 COMMISSION
 KANSAS

PLUGGING
 FILE SEC 6-21-13W
 BOOK PAGE 94 LINE 15