

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 6 Twp. 21 Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines SW NE SW

Lease Owner Barnstrom Oil Company, Inc.

Lease Name Schartz "A" Well No. 1

Office Address P. O. Box 1796, Amarillo, Texas 79105

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 7, 19 69

Application for plugging filed (Letter 6-10-69) June 7, 19 69

Application for plugging approved June 7, 19 69

Plugging commenced June 7, 19 69

Plugging completed June 7, 19 69

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3625 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	246	8-5/8"	246'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 450 feet. Set first plug @ 450 feet with 50 sacks cement.
Filled hole with heavy mud to 210 feet. Set second plug @ 210 feet with 25 sacks cement.
Filled hole with heavy mud to 40 feet. Set third plug @ 40 feet with 1/2 sack hulls and 10 sacks cement. Job complete @ 10:00 AM, June 7, 1969. Used pump truck to pump cement through drill pipe to plug.

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Place - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss. E. E. Hall

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

830 Sutton Place - Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 10 day of June 19 69

Barbara J. Layton
Barbara J. Layton Notary Public.

My commission expires Feb. 1, 1972.



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

SCHARTZ "A" #1
SW NE NW Section 6-21S-13W
Stafford County, Kansas

Commenced: May 29, 1969
Completed: June 7, 1969

OPERATOR - Barnstrum Oil Company, Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	20	Surface clay	
20	100	Sand	
100	246	Sand and shale	Ran 12 joints of 8-5/8" casing, set @ 246' w/250 sacks cement.
246	675	Sand, shells and sand streaks	
675	795	Shale and shells	
795	830	Anhydrite	
830	1350	Shale and shells	
1350	3275	Lime and shale	
3275	3390	Lime	
3390	3480	Lime and shale	
3480	3591	Lime	
3591	3625	Arbuckle	
3625	TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1969
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the SW NE NW Section 6-21S-13W, Stafford County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 10 day of June, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

