

COPY

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Morrison Trust

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Paul L. Bandy

SEC. 6 TWP. 21S RGE. 13W (E) or (W)

ADDRESS P.O. Box 364 Canton, KS, 67428

COUNTY Stafford

PHONE# (316) 628-4417 OPERATORS LICENSE NO. 5990

Date Well Completed

Character of Well oil

Plugging Commenced 6-26-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-7-89

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3664'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				85/8"	255	none
				4 1/2"	3232	2123

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 2918' dumped 5 sacks of cement shot 2400'
2123' pulled 65 joints, plugged surface with 300# hulls, 10 sacks gel,
50 sacks cement, 10 sacks gel, 100 # hulls, 100 sacks cement 60/40
poz 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Paul L. Bandy

STATE OF Kansas COUNTY OF Rice, ss.

JUL 13 1989
9-13-1989

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 13 day of July, 19 89

Notary Public

My Commission Expires:



15.185.21353.0000

DRILLERS'
WELL LOG

DATE COMMENCED: August 29, 1981
DATE COMPLETED: September 5, 1981

National Oil Co.
MORRISON Trust #2
NE NW SE
Sec 6-T215-R13W
Stafford County, Kansas

0 - 143' Surface Soil, Sand
143 - 161' Hard Sand
161 - 340' Shale, Sd Streaks, Red Bed
340 - 791' Red Bed
791 - 814' Anhydrite
814 - 2829' Red Bed, Shale, Lime
2829 - 3201' Lime
3201 - 3220' Shale & Lime
3220 - 3238' Lime
3238 - 3318' Shale
3318 - 3328' Lime & Shale
3328 - 3539' Lime
3539 - 3664' Shale, Lime
3664' RTD

ELEVATION: 1911K.B.

FORMATION DATA

ANHYDRITE	791
TOPEKA	2829
HEEBNER	3201
TORONTO	3220
DOUGLAS	3238
BROWN LIME	3318
LANSING KC	3328
BASE KC	3539
RTD	3664

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1981
CONSERVATION DIVISION
Wichita, Kansas

SURFACE PIPE: Set new 23#
8-5/8" pipe at 255' w/200
sacks 60/40 pozmix w/20/0
Gel, 3% cc.

PRODUCTION PIPE: Set used 4 1/2"
pipe, 10 1/2# at 3232' w/200 sacks
pozmix.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Braney, of lawful age does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Bill Braney

Subscribed and sworn to before me this 14 day of September 1981

My Comm. Expires:
April 11, 1982

Louise M. Wagner