

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form 11-1

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

			X

Locate well correctly on above
Section Plat

Stafford County, Sec. 6 Twp. 21 Rge. 13 (E) W (W)
 Location as "NE/CNWSW" or footage from lines NW NE SE
 Lease Owner Woodman - Iannitti Drlg. Co.
 Lease Name Morrison Well No. #3
 Office Address 1008 Union Nat'l Bldg. ; Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed 19
 Application for plugging filed February 19 74
 Application for plugging approved February 19 74
 Plugging commenced February 22 19 74
 Plugging completed March 1 19 74
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
 Producing formation Depth to top Bottom Total Depth of Well Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250	None
				5 1/2"	3598	2800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

February 22, 1974 Plugged off bottom. Sun Oil Well Cementing Co. mixed and pumped 25 sx of cement.
 March 1, 1974 Plugged off top. Set 10" rock bridge at 250'. Filled 8 5/8" surface casing from 250' to base of cellar with 3000 lb. P.S.I. ready-mix concrete.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 12 1974
 CONSERVATION DIVISION
 Wichita, Kansas

Name of Plugging Contractor, RUSS CASING PULLING, INC.
 Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF SEDGWICK ss.
 K. T. WOODMAN (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
 (Signature) K. T. Woodman
 1008 Union National Bldg. (Address)
 Subscribed and Sworn to before me this 1st day of March 19 74

My commission expires Feb. 11, 1976

Justina Chamberlain
 Justina Chamberlain Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1973

CONSERVATION DIVISION
Wichita, Kansas

15.185.01690.0000

Tulsa, Oklahoma
March 17, 1953

Sunray Oil Corporation
Tulsa, Oklahoma

Contractor: Stickle Drilling Company
Drilling commenced: February 27, 1953
Drilling completed: March 15, 1953

Morrison No. 3 NW-NE-SE
Section 6-21S-13W,
Stafford County, Kansas

DRILLERS LOG

Sand & Surface Clay	0-270
Red Bed Shale	270-780
Anhydrite	780-840
Red Bed Shale	840-930
Shale & Shells	930-1680
Lime	1680-1790
Lime & Shale	1790-1960
Shale & Lime	1960-2110
Lime & Shale	2110-2250
Shale & Lime	2250-2360
Shale & Lime Breaks	2360-2565
Shale & Lime	2565-2717
Lime & Shale	2717-2785
Shale & Lime	2785-2995
Lime & Shale	2995-3068
Shale & Lime	3068-3136
Lime	3136-3205
Shale & Lime	3205-3338
Lime & Shale	3338-3420
Lime	3420-3603 TD

I, Frank E. Stickle hereby certify the above to be a true and complete
drillers log of Sunray Oil Corporation's Morrison No. 3 NW-NE-SE-
Section 6-21S-13W, Stafford County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956
My commission expires