


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 6 Twp. 21 Rge. 13 (E) (W)X  
Location as "NE/CNW/SE" or footage from lines W/2-SW/SE  
Lease Owner Woodman-Iannitti Drilling Co.  
Lease Name MORRISON SWD Well No. 1  
Office Address P. O. Box 308, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ October 9, 1974  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced \_\_\_\_\_ October 28, 1974  
Plugging completed \_\_\_\_\_ November 14, 1974  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2120 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	810	-0-
				5 1/2	1824	1260.64'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Pushed a plug to 1800'. Dumped 20' of sand and 5 sacks cement. Shot casing at 1275'. Pulled a total of 38 jts. of 5 1/2" casing. Pushed a plug to 300' and built a rock bridge. Plugged well with 5 yards readymix concrete.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Rockhold Engn. (If additional description is necessary, use BACK of this sheet)  
Address P. O. Box 598, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (~~owner~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold  
Box 698, Gt. Bend, Ks. 67530 James W. Rockhold  
(Address)

3rd day of December, 1974

Cathy Miller  
Cathy Miller Notary Public.

15.185-11756.0000

Morrison #1 Well  
Sec. 6-21S-13W, Stafford County, Kansas

Drilled for: Sunray Oil Corporation  
Drilled by: Mouser Drilling Company

Drilling Commenced: November 23, 1950  
Drilling Completed: December 9, 1950

Casing Record:

8 5/8" 810' 8 rd thd 2 1/4" Casing  
5 1/2" 3616 1/2' 8 rd thd 1 1/4" Casing

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
Surface clay and sand	130
Clay and sand	260
Grey shale	300
Sand	340
Red Bed	570
Shale and shells	750
Red Bed	793
Anhydrite	825
Red bed	950
Shale and shells	1185
Salt	1400
Shale and shells	1615
Lime	1735
Lime and shale	1835
Sandy lime	1900
Shale and lime	1925
Lime	2025
Lime and shale	2110
Shale and lime	2355
Shale and shells	2465
Shale	2570
Shale and lime	2700
Lime and shale	2730
Shale and lime	2840
Lime	2915
Lime and shale	2930
Lime	2984
Broken Lime	3030

<u>FORMATION</u>	<u>DEPTH</u>
Lime	3142
Shale and lime	3195
Lime and shale	3297
Shale	3320
Lime	3542
Shale	3616
Arbucklo	3618
Total Depth	3618'

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 15 1974  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the above described location to the best of my knowledge and belief.

B. L. Mouser

Subscribed and sworn to before me this 19th day of December 1950.

My Commission Expires:

March 18 1950

Francis L. Webber