

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Finney SEC. 5 TWP. 21S RGE. 33W E/W
 Location as in quarters or footage from lines:
C NE NW

Lease Owner George Jones
 Lease Name CAMPBELL Well No. 1
 Office Address 125 N. Market, Suite #1210, Wichita, KS
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry ⁶⁷²⁰²
 Date Well Completed September 21, 1982
 Application for plugging filed September 21, 1982
 Plugging commenced September 21, 1982
 Plugging completed September 21, 1982
 Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? YES

Locate Well
 correctly on above
 Section Platt.

Name of Conservation Agent who supervised plugging of this well _____
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4800'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 1200' with 70 sx.
Set 2nd plug @ 420' with 40 sx.
Set 3rd plug @ 40' Sol. Bridge with 10 sx.
10 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS
 (Address) 67202

SUBSCRIBED AND SWORN TO before me this 27th day of Sept., 19 82

My Commission expires: 7-13-85

RECEIVED
 Elizabeth Terry Notary Public
 STATE CORPORATION COMMISSION
 SEP 30 1982
 CONSERVATION DIVISION
 Wichita, Kansas

NOTARY PUBLIC
 ELIZABETH TERRY
 STATE OF KANSAS

CONTRACTORS WELL LOG

OPERATOR: George Jones
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: CAMPBELL #1
 LOCATION: C NE NW, Sec. 5-21S-33W
 Finney County, Kansas
 SPUD DATE: 9/13/82
 COMPLETION DATE: 9/21/82

0	407	Sand & Shale
407	480	Shale
480	1973	Sand & Shale
1973	2098	Shale
2098	2113	Anhydrite
2113	2775	Shale
2775	4800	Lime & Shale
	4800	Rotary Total Depth

Spud hole @ 7:00 p.m., 9/13/82. Drilled 407' of a 12 1/4" hole. Ran 10 jts. of 8 5/8" 20# casing (tally 399.49') set @ 406.49' and cemented with 280 sx. Class A, 2% gel, 3% c.c. Plug was down @ 6:00 a.m., 9/14/82.

4800' RTD. Set 1st plug @ 1200' with 70 sx. Set 2nd @ 420' with 40 sx. Set 3rd plug @ 40' Sol. Bridge with 10 sx. 10 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c.

SAMPLE TOPS:

Anhydrite 2098'
 B/Anhyd. 2113'

RECEIVED
 STATE CORPORATIONS COMMISSION
 SEP 30 1982
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas)
) SS
 County of Sedgwick)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the CAMPBELL #1, C NE NW, Sec. 5-21S-33W, Finney County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public in and for the aforesaid county and state, as of this 27th day of September, 1982.

Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my commission expires 7-13-85

