15-009-06631-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County. Sec. 34 Twp. 16 Rge. (E) 12 (W)
Location as "NE/CNW¼SW¼" or footage from lines NW¼ NW¼ NE¼
Lease Owner Lewis Drilling Company, et al
Lease Name Feltes Well No. 1
Office Address 607 Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-24-51 19
Application for plugging filed 8-24-51 19
Application for plugging approved 8-27-51 19
Plugging commenced 8-24-51 19
Plugging completed 8-24-51 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3375 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	147'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

20 Sx Cement @ 147'
5 Sx Cement on Top

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company
Address 607 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. L. Bailey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Bailey
9-6-51
SEP 6 X 1951
607 Union National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of August, 19 51.
Arthur R. Derrington
Notary Public.

My commission expires August 20, 1952.

23-8390-s 6-51—20M

PLUGGING
FILE SEC 34 T 16 R 12W
BOOK PAGE 10 LINE 1

15-009-06631-00-00

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Lewis Drilling Company, et al

SEC. 34 T. 16 R. 12W

FARM Feltes NO. 1

LOC. NW¼ NW¼ NE¼

TOTAL DEPTH 3375'

COMM. 8-13-51 COMP. 8-24-51

COUNTY Barton

KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

CASING

20	10	
15	X 8 5/8" 147'	
12	6	
13	5	

ELEVATION 1895 DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 95	Clay
95 - 195	Blue Shale
195 - 225	Sand
225 - 325	Red Bed
325 - 780	Shale & Shells
780 - 800	Anhydrite
800 - 1135	Red Bed Shale
1135 - 1425	Shale & Shells
1425 - 1920	Broken Lime
1920 - 2240	Shale & Shells
2240 - 2430	Shale
2430 - 2590	Shale & Broken Lime
2590 - 2625	Lime & Shale
2625 - 2651	Shale
2651 - 2810	Lime & Shale
2810 - 2863	Lime
2863 - 2900	Lime & Shale
2900 - 2965	Lime
2965 - 3035	Lime & Shale
3035 - 3063	Shale
3063 - 3375	Lime
3375 - TD	

GEOLOGICAL TOPS

Heebner	2972'
Lansing-Kansas City	3077'
Basal Penn. Conglomerate	3338'

STATE OF KANSAS) SS.
COUNTY OF SEDGWICK)

L. L. Bailey, Lewis Drilling Company, of lawful age, being first duly sworn under oath, states that the Lewis Drilling Company was the Contractor engaged for the drilling of the Feltes No. 1, located in the Northwest Quarter of the Northwest Quarter of the Northeast Quarter (NW¼ NW¼ NE¼) of Section 34, Township 16, Range 12 West, Barton County, Kansas, and that the foregoing log is a true and correct copy of the completed well.

LEWIS DRILLING COMPANY

By L. L. Bailey
L. L. Bailey

Subscribed and sworn to before me, a Notary Public, in and for the county and state above mentioned, this 30th day of August, 1951.

Arthur P. Dennington
Notary Public

RECEIVED
COMMISSION
SEP 6 X 1951
CONSERVATION DIVISION
Wichita, Kansas

My commission expires August 20, 1952.

PLUGGING
FILE SEC 34 T 16 R 12W
BOOK PAGE 106 LINE 1