

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County, Sec. 34 Twp. 16 Rge. 12 (E) (WX)

Location as "NE/CNW%SW%" or footage from lines Approx N/2 SE NW

Lease Owner Jay Bergman Oil Co.

Lease Name #5 Tinkel Well No. #5

Office Address 425 Union Center Building Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) (Oil) Dry hole

Date well completed 2/6/57 19

Application for plugging filed 2/12/59 19

Application for plugging approved 2/17/59 19

Plugging commenced 19

Plugging completed 19

Reason for abandonment of well or producing formation Not producing oil

If a producing well is abandoned, date of last production February 1958

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3354 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded from 3290' to 310' rock bridge 310' to 300' run 25 sacks cement 300' to 225' mudded from 225' mudded from 225' to 35' rock 35' to 30' run 10 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 12 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jay Bergman Oil Company

Address 425 Union Center Building Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Harold Bergman (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman  
425 Union Center Bldg. Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11<sup>th</sup> day of March, 1959

My commission expires October 15, 1962 Judith L. Palmer Notary Public.

PLUGGING  
FILE SEC. 34 T. 16 R. 12W  
BOOK PAGE 15 LINE 7

WELL LOG

Date Started: 1-28-57  
Date Completed: 2-6-57

Tinkel No. 5  
N/2 N/2 SE/4 NW/4  
34-16-12  
Barton County, Kansas

Elevation	1887 K.B.
Anhydrite	771' (-1116)
Heebner	2966' (-1079)
Brown Lime	3057' (-1170)
Kansas City	3072' (-1185)
Arbuckle	3348' (-1461)
R.T.D.	3354' (-1467)

5 1/2" set at 3351'

0'	-	38'	Surface Clay and Rock
38'	-	45'	Sand
45'	-	120'	Shale
120'	-	140'	Sand
140'	-	250'	Shale
250'	-	260'	Sand
260'	-	375'	Shale
375'	-	420'	Sand
420'	-	490'	Shale
490'	-	771'	Red Bed
771'	-	798'	Anhydrite
798'	-	1250'	Shale and Shells
1250'	-	1400'	Salt and Shale
1400'	-	1605'	Shale and Shells
1605'	-	1790'	Shale, Shell and Lime
1790'	-	2025'	Lime and Shale
2025'	-	2700'	Lime and Shale
2700'	-	2845'	Lime
2845'	-	2966'	Lime
2966'	-	3057'	Heebner
3057'	-	3072'	Lime
3072'	-	3290'	Kansas City
3290'	-	3348'	Lime
3348'	-	3354'	Arbuckle
			R.T.D.

**RECEIVED**  
STATE CORPORATION COMMISSION  
FEB 12 1959  
CONSERVATION DIVISION  
Wichita, Kansas

AFFIDAVIT

State of Kansas . . . . . County of Barton

I, Cecil M. Olson, employee of the owner, do swear that the statements and matter herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

BY: Cecil Olson

Subscribed and sworn before me this 1st day of March, 1957.

John E. Stinson  
NOTARY PUBLIC

My commission expires: June 24, 1959

PLUGGING	
FILE	SEC 34 T. 16 R. 2W
BOOK	PAGE 15 LINE 7