


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 34 Twp. 16 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE/4 SW/4 NE/4
Lease Owner Shields Oil Producers, Inc.
Lease Name Feltes Well No. 3
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil well
Date well completed February 2 19 56
Application for plugging filed March 28 19 66
Application for plugging approved March 29 19 66
Plugging commenced May 19 19 66
Plugging completed May 31 19 66
Reason for abandonment of well or producing formation Depleted oil well

If a producing well is abandoned, date of last production April 19 66
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,338 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	Cmtd. w/100 sax
				4 1/2"	3,336'	2,905'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3,338 feet to surface feet for each plug set.

Pumped 15 sax cement to bottom
Shot of pipe @ 2,905' and pulled
Set bridge plug @ 200'
Dump 3 yds. cement on plug to cellar

RECEIVED
STATE CORPORATION COMMISSION
JUL 5 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.
Address P. O. Box 313, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
R. J. Shields (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. J. Shields
Shields Bldg., Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of July, 19 66

My commission expires May 26, 1967


Leuch Phillips
Notary Public.



WELL LOG

Operator: Shields Oil Producers
Well: Feltus #3
Commenced: January 23, 1956
Completed: February 2, 1956
Contractor: Shields Drilling Co., Inc.

Well Description: NE SW NE
Sec. 34-16-12W
Barton County, Kansas



CASING RECORD

Size	Run	Pulled
8 5/8"	200'	Cmtd. with 100 cas
4 1/2"	3336'	Cmtd. with 100 cas

Elevation: 1877' RB
Treatment: 500 GAL. ACID
Production: 25 BOPD /ARB.

Tops:	Depth
Topoka	2665'
Hochbar	2951'
Toronto	2965'
Brown Lime	3040'
Lansing-K. C.	3057'
Conglomerate	3321'
Arbuckle	3334'

..... Figures Indicate Bottom of Formations

Top Soil and Clay	20
Shale & Shells	100
Shale & Lime Streaks	200
Shale	340
Sand	420
Shale & Red Bed	580
Red Bed	760
Anhydrite	790
Red Bed & Shale	1000
Shale	1050
Shale Shells & Salt	1320
Shale	1420
Shale & Lime	1475
Lime & Shale	1645
Shale & Lime	1755
Lime & Shale Streaks	1800
Lime & Shale	2310
Shale	2500
Shale & Lime Streaks	2640
Lime & Shale	2810
Lime	2899
Lime & Shale	2966
Shale & Lime	3051
Lime	3334
Arbuckle Dolomite	3336 RTD

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1966

CONSERVATION DIVISION
Wichita, Kansas

DST #1-5045-91/1 hr. Rec. 220' gas, 140' slightly oil & gas cut mud, 200' heavily oil cut mud, 180' slightly muddy oil, IFF-120#, FFF-220#, BHF-9900/20 min.

Notes