


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Barton County, Sec. 34 Twp. 16 Rge. 12 (E) W (W)
Location as "NE/CNW&SW" or footage from lines NE NW NE
Lease Owner Shields Oil Producers, Inc.
Lease Name Feltes Well No. 4
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil well
Date well completed October 23 1957
Application for plugging filed January 4 1968
Application for plugging approved January 5 1968
Plugging commenced March 25 1968
Plugging completed April 8 1968
Reason for abandonment of well or producing formation Depleted oil well

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	323'	Cmtd. w/ 200 sax
				4 1/2"	3,335'	2,836'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3,300 feet to surface feet for each plug set.
Sanded hole to 3,050', dump 5 sacks of cement on bottom. Pulled pipe from hole. Set bridge at 520', filled hole with 5 yds. of cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.
Address P.O. Box 313, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
R. J. Shields (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
Shields Bldg., Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of April, 1968

Keith Phillips

My commission expires May 26, 1971 Notary Public.




15-009-07413-00-00
Shields

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers
Well: Feltes #4
Commenced: October 13, 1957
Completed: October 23, 1957
Contractor: Shields Drilling Co., Inc.

Well Description: NE NW NE
Sec. 34-16S-12W
Barton County, Kansas



CASING RECORD		
Size	Run	Pulled
8 5/8"	323'	Cmtd. w/200 sax.
4 1/2"	3335'	Cmtd. w/100 sax.

Elevation: 1894' RB
Treatment: 500 gal Acid 1 st. Treatment
1500 gal Acid 2 nd. Treatment
Production: 25 BOPD

JAN 5 1959

Tops:	Topeka	2678'
	Heebner	2962'
	Toronto	2979'
	Brown Lime	3052'
	Lansing-K. C.	3070'
	Basal Penn. Sand	3327'
	Arbuckle	3331'

..... Figures Indicate Bottom of Formations ...

Shale & Clay	591'
Red Bed	768'
Anhydrite	800'
Red Bed, Shale & Shells	1100'
Lime w/Shale Streaks	1810'
Lime	2060'
Shale w/Lime Streaks	2227'
Shale	2438'
Shale w/Lime Streaks	2688'
Lime w/Shale	2847'
Lime	3336' RTD

Notes

DST #1 3071-3105 Tool open 1 hr., gas to surface in 17 min. Rec. 75' gassy oil specked mud, 505' clean oil, 5' water BHP-880#/20 min.
DST #2 3127-3145 Tool open 1 hr. w/fair blow thruout. Rec. 95' watery mud. BHP-940#/20 min.