

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-009-19071-00-00

API NUMBER 15-009-22,878
LEASE NAME Feltes
WELL NUMBER B-1
 Ft. from S Section Line
 Ft. from E Section Line
SEC. 150' W of SE SW NE
TWP. RGE. (E) or (W)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Davis Petroleum, Inc.
ADDRESS Rt. 1 Box 183B
Great Bend, Kansas 67530
PHONE# (316) 793-3051 OPERATORS LICENSE NO. 4656

COUNTY Barton
Date Well Completed
Plugging Commenced 7-27-87
Plugging Completed 8-11-87

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3384'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	265'	none
				5-1/2"	3384'	1480'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 3275' and 5 sacks cement. Shot pipe @2605', 2003', 1480', pulled a total of 47 joints of 5-1/2" casing. Plugged surface with 5 sacks hulls and 100 sacks econolite.
Plugging Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 13th day of August, 19 87

 Notary Public

My Commission Expires:



AUG 17 1987
8-17-1987 Form CP-4
CONSULTATION DIVISION
Wichita, Kansas
Revised 07-86

15-009-19071-00-00

GEOLOGICAL REPORT

Associates Oil & Gas, Inc.
#1-B Feltes
150' West of SE-SW-NE
of Section 34-16S-12W
Barton County, Kansas

September 15, 1982

Elevation: 1870 GL
1880 KB

Geologist: James L. Crisler
Commenced: August 27, 1982
Completed: September 3, 1982
Contractor: Husky Drilling Company, Inc.
Casing Record: 8 5/8" Surface at 265' w/165 sx. 60-40
Pozmix, 2% Gel, 3% CaCl, 5 1/2" production
at 3384 w/100 sx Common (ASC)
Hole Size: 7 7/8"
Samples: 10' from 2600' to RTD
Drill Time: 1' from 2600' to RTD
Electric Log: Gamma Ray, Neutron & Caliper
Drill Stem Tests: Two--See Significant Shows
Total Depth: 3385' RTD

FORMATION TOPS AND SIGNIFICANT SHOWS
(All Measurements from Kelly Bushing)

	<u>Drill Time/Samples</u>	<u>Electric Log</u>
Anhydrite	760' (+1120)	-----
Topeka	2671' (- 791)	1673 (- 793)
Heebner	2955' (-1075)	2956 (-1076)
Toronto	2971' (-1091)	2972 (-1092)
Brown Lime	3047' (-1167)	3047 (-1167)
Lansing	3063' (-1183)	3066 (-1186)
Conglomerate	3308' (-1428)	3304 (-1424)
Reworked Arb.	3321' (-1441)	3316 (-1136)
Arbuckle	3326' (-1446)	3322 (-1442)
RTD	3385' (-1505)	

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1987

Oil and Gas Division