

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

APR 29 1966

CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Quality Oil CompanyComplete Address: 6320 Jacqueline, Wichita, KansasLease Name Newcombe "B" Well No. # 2Location NE SW NW Sec. 5 Twp. 21 Rge. 13 (E) (W) WCounty Stafford Total Depth 3640'Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 10:45AM Day 28th Month April Year 1966

The Above well was plugged as follows:

217' of 8 5/8" surface pipe, cement circulated. 3639' of 4 1/2" long string,
cemented with 75 sacks. Top perforation 3584'. Bottom of the hole was sand-
ed to 3575', and cemented with 4 sacks, through the dump bailer. 3006' of
4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid
to 217', rock bridge from 217' to 207'. 9 sacks of cement was mixed in a
barrel, and put on plug at 207', through the dump bailer, and let set over-
night. Next day hole was bailed dry, and 16 sacks of cement was added to the
plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging SupervisorDATE 4/29/66
INV. NO. 3130-W