

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Quality Supply Company

Complete Address: 6320 Jacqueline, Wichita, Kansas

Lease Name Newcombe "B" Well No. # 1

Location SE SE NW Sec. 5 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3629'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:15 AM Day 2nd Month May Year 1966

The Above well was plugged as follows:

212' of 8 5/8" surface pipe, cement circulated. 3628' of 5 1/2" long string,
cemented with 100 sacks. Top perforation 3438'. Bottom of the hole was
sanded to 3400', and cemented with 5 sacks. 2895' of 5 1/2" long string was
recovered from the hole. Bridge plug was pushed in fluid to 212', rock
bridge from 212' to 200'. 5 sacks of cement was mixed in a barrel, and put
on plug at 200', through the dump bailer, and let set over-night. Next day
hole was bailed dry, and 20 sacks of cement was added to the plug. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10
sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Aubie Elving
Well Plugging Supervisor

DATE 5/5/66

INV. NO. 3166-W