

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1964

CONSERVATION DIVISION
Wichita, Kansas

12-9-1964

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bovaird Supply Company

Complete Address: Box 897, Great Bend, Kansas

Lease Name Gibson Well No. # A-1

Location N/2 NW Sec. 3 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3579

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Apex Casing Pulling Co., Inc.

Address: 739 East Second, Hoisington, Kansas License No. 544

Operation Completed: Hour 2:30PM Day 7th Month Dec. Year 1964

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cement circulated. 3568' of 5 1/2" long
string, cemented with 125 sacks. Bottom of the hole was sanded to 3550',
and cemented with 5 sacks. Fluid level was up in the hole. Bridge plug
was set at 200', and 10' of rock bridge. 20 sacks of cement was mixed
in a barrel, and put on plug at 190' through the dump bailer. And let
set over-night. Next morning hole was bailed dry, and 5 sacks of cem-
ent was added to the plug. Hole was filled with mud to 40', and 10' of
rock bridge, and cemented with 10 sacks to the base of the cellar. 2707'
of 5 1/2" long string was recovered from the hole. 2242' was last shot on pipe.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/9/64

INV. NO. 309-10