

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Co.

Complete Address 217 N. Water Wichita, Ks

Lease Name C.J. Schaeffer Well No. 3

Location SE/SE/SW Sec. 3 Twp. 21 Rge. 13 (E) W

County Stafford Total Depth 3593

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 1:00 PM Day 16 Month 6 Year 1971

The above well was plugged as follows:

206 ft 10 3/4 surface pipe cemented with 200 sacks. 3592 ft 7" long
string cemented with 300 sacks. Top perf. 3287 ft. Sand back to
3260 ft, 6 sacks cement with bailer. Pulled 1898 ft 7". Pump 4
sacks hulls, 25 sacks gel., 150 sacks cement to surface.

Pumped by Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

Signed: *H. Russell Silvestro*
Well Plugging Supervisor

INVOICED

DATE 6-18-71

INV. NO. 3874-W