

15.185.12161.0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1966

CONSERVATION DIVISION
Wichita, Kansas

8-22-1966

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Aspen Drilling Company

Complete Address: P. O. Box 783, Great Bend, Kansas

Lease Name Thul Well No. # 1

Location SW NW ^{NE} ~~NW~~ Sec. 23 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3700'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:30AM Day 16th Month August Year 1966

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cemented with 250 sacks. 3603' of 4 1/2" long
string, cemented with 124 sacks. Plug back T.D. 3590'. Top perferation 3560'.
Bottom of the hole was sanded to 3550', and cemented with 3 sacks. 2700' of
4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid
to 240', rock bridge from 240' to 230', 10 sacks of cement was mixed in a barrel
and put on plug at 230', through the dump bailer, and let set for 6 days. Hole
was bailed dry and 15 sacks of cement was added to the plug. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to
the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-22-66

INV. NO. 2789-W