

15.195.00236.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Trego County, Sec. 2 Twp. 11 Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines NENESE 1/2
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Webb "B" Well No. 1
Office Address 909 Palace Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 26, 19 58
Application for plugging filed January 26, 19 58
Application for plugging approved January 26, 19 58
Plugging commenced January 26, 19 58
Plugging completed January 26, 19 58
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3733 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	180	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole with heavy rotary mud to 600 ft., and cemented with 25 sacks of cement through drill pipe. Mudded hole with heavy mud to 200 ft., set plug and cemented with 15 sacks of cement through drill pipe. Mudded hole to 40 ft., set plug and 1/3 sack of hulls and cemented with 10 sacks of cement to surface.

(If additional description is necessary, use BACK of this sheet).

Name of Plugging Contractor H-30, Inc.
Address 709 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick
L. C. Sponenberg ^{ss.} employee of contractor
(employee of owner, or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 58

My commission expires February 13, 1960.

Rose Fussey
Notary Public.

PLUGGING
FILE SEC 2 T 11 R 214
BOOK PAGE 78 LINE 30

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1958

CONSERVATION DIVISION


KANSAS GEOLOGICAL SOCIETY 15.195.00236.00.00
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser, Oil Producer**
 FARM **Webb #3D** NO. **1**

SEC. **2** T. **11** R. **21**
 LOC. **HEBNER**

TOTAL DEPTH **3733'**
 COMM. **1/15/58** COMP. **1/26/58**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED

COUNTY **Trego**



CASING		
20	10	
15	8	180'
12	6	
13	5	

2083 **FD**
 ELEVATION 2080 **17**
 2078 **07**
 PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	35
Shale with clay and sand streaks	100
Shale	180
Shale and Shells	335
Shale	460
Shale with streaks of sand, Iron Pyr.	1025
Sand	1255
Shale and Shells	1520
Anhydrite	1568
Shale and Shells	1920
Shale with lime streaks	2075
Lime & Shale	2550
Shale & Shells	2750
Shale and Lime	3394
K. C. Lime	3598
Lime & Shale	3644
Lime-Shale-Conglomerate	3659
Arbuckle	3733

FORMATION TOPS:

Hebner	3327'
Lansing	3365'
Arbuckle	3658'

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.
 By *L. C. Spohnberg*
 L. C. Spohnberg

STATE OF KANSAS)
) SS
 COUNTY OF **WYDOGICK**)

Subscribed and sworn to before me, a notary public, in and for said county and state this 29th day of January 1958.

For Tusey

My Commission expires February 13, 1960.

PLUGGING
 FILE SEC 2 T. 11 R. 21
 BOOK PAGE 78 LINE 30

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 1 1958
 CONSERVATION DIVISION
 Wichita, Kansas