


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

*Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blizag Building
Wichita, Kansas

Trego County. Sec. 1 Twp. 11S Rge. 21W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE SW
Lease Owner Imperial Petroleum Company, Inc.
Lease Name Spaulding Well No. 1
Office Address 903 Union Nat'l. Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 31 19 51
Application for plugging filed December 31 19 51
Application for plugging approved December 31 19 51
Plugging commenced December 31 19 51
Plugging completed December 31 19 51
Reason for abandonment of well or producing formation Oil in commercial quantities not found.
If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? - Yes -



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326 Hays, Kansas
Producing formation - - Depth to top - - Bottom - - Total Depth of Well 3740' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	253'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240'. Set #1 Plug W/15 Sacks Cement. Filled hole with heavy mud to 40'. Set #2 Plug W/10 Sacks Cement to Bottom Cellar.

RECEIVED
STATE CORPORATION COMMISSION
JAN - 9 1952
CONSERVATION DIVISION
WICHITA, KANSAS
1-9-1952

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Imperial Petroleum Company, Inc.
Address 903 Union National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL PETROLEUM COMPANY, INC.
(Signature) By: Raymond L. Bacon Sec.-Treas.
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 52

My commission expires January 4, 1954
Marguerite Little Notary Public.

PLUGGING 29-3278-S 4-50-10M
FILE SEC-11-216
BOOK PAGE 135 LINE 21

DRILLER'S LOG

Imperial Petroleum Company, Inc.
903 Union Nat'l. Bank Bldg.
Wichita 2, Kansas

Spaulding #1
SW SE SW Sec. 1-11S-21W
Trego County, Kansas

Total Depth: 3740'

Date Commenced: 12-19-51 Date Completed: 12-31-51

Contractor: Imperial Petroleum Company, Inc., Wichita, Kansas

Casing Record: Set 253' of 8 5/8" Surface Casing W/175 Sacks Cement.

Elevation: 2088 R.B.
Production: D & A

Figures indicate bottom of formations:

Sand & Clay	90'		
Shale & Shells	650'		
Sand & Shale	775'		
Shale, Shells & Sand	1485'		
Shale & Shells	1530'		
Anhydrite	1575'		
Shale & Shells	2130'		
Lime	2180'		
Lime & Shale	3345'		
Lime	3619'		
Conglomerate	3740'		
Rotary Total Depth	3740'		

		<u>TOPS</u>	
Heebner	3343		(-1255)
Toronto	3364		(-1276)
Lans.-K.C.	3383		(-1295)
Conglomerate	3618		(-1530)
Total Depth	3740		(-1652)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL PETROLEUM COMPANY, INC.

JAN - 9 1952
CONGREGATIONAL CHURCH
WICHITA, KANSAS

By: C. R. Mayfield
C. R. Mayfield, Geologist

Subscribed and sworn to before me this 7th day of January, 1952.

W. Eugene Little
Notary Public

My Commission Expires:

January 4, 1954

PLUGGING
FILE SEC 1711 R-21
BOOK PAGE 35 LINE 21