


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bigging Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 3 Twp. 21 Rge. 13 (SE) W (W)
Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner Hilton Drilling Company, Inc.
Lease Name Jung Well No. 2
Office Address 2421 Tenth Street, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed December 11, 1954
Application for plugging filed December 27, 1954
Application for plugging approved -- 19
Plugging commenced December 29, 1954
Plugging completed January 1, 1955
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 3600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	131	8-5/8"	131	None
		0	3599	5-1/2"	3599	2554

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock to 3300', pumped in 5 sacks cement.
Plugged surface with pump truck (Halliburton), mixed and pumped
in 8 sacks Gel Mud; put in plug.
Mixed and pumped in 100 sacks cement.
Shut in well.


RECORDED
STATE CORPORATION COMMISSION
JAN 6 1955 1-6-1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ace Pipe Pulling Company
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Dan H. Cook, Vice-President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan H. Cook Vice-Pres.
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of January 19 55.
Carmen Reinhardt Leiber
Notary Public.



D R I L L E R ' S L O G

COMPANY: HILTON DRILLING COMPANY, INC. LOCATION: SE of SW of NW
 Sec. 3-21S-13W
 CONTRACTOR: HILTON DRILLING COMPANY, INC. Stafford County, Kansas
 FARM NAME: JUNG NO. 2 ELEVATION: 1882 D.F.
 COMMENCED: 11/25/54 Casing Used: 8-5/8 @ 131' w/175 sx.
 COMPLETED: 12/11/54 5-1/2 @ 3599' w/125 sx.

Clay and Sand	105
Shale	125
Hard Sand	146
Shale	225
Sand	255
Shale and Sand	360
Red Bed and Shale	738
Anhydrite	762
Shale, Red Bed and Shells	1015
Shale and Shells	1510
Shale, Lime and Shells	1665
Shale and Lime	1810
Shale Streaks and Lime	1970
Shale and Lime	2797
Lime	2885
Shale and Lime	2958
Lime	3040
Shale and Lime	3097
Lime	3233
Shale and Lime Streaks	3255
Lime	3600
Total Depth	3600

STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

Henry Peacock
 Henry Peacock, Secretary

Subscribed and sworn to before me this 13th day of December, 1954:

My commission expires: 1-26-55

Carmen Conrad Zeiler
 Notary Public

RECEIVED
 STATE OF KANSAS
 DECEMBER 14 1954
 GEORGE W. HILTON
 Notary Public

PLUGGING
 FILE NO. 3-21-13W
 BOOK PAGE 87 LINE 37