


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Stafford County, Sec. 3 Twp. 21S Rge. 13 (E) W(W)

Location as "NE/CNW%SW%" or footage from lines SW NW SW  
Lease Owner Hilton Drilling Company, Inc. et al  
Lease Name Schaeffer Well No. 1  
Office Address 925 Patton Road (P. O. Box 108), Great Bend, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil well  
Date well completed September 11, 19 53  
Application for plugging filed July 31 19 59  
Application for plugging approved August 3 19 59  
Plugging commenced August 17, 19 59  
Plugging completed August 22, 19 59  
Reason for abandonment of well or producing formation Well no longer capable of commercial production  
If a producing well is abandoned, date of last production July 19 59  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas  
Producing formation Lansing Kansas City Depth to top 3339 Bottom 3343 Total Depth of Well 3564 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	216'	None
				5-1/2"	3564'	2715'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug back with sand to 3325' - mix and dump 5 sacks cement (to 3285'). Pull 2715' 5-1/2 casing. Plug surface with pump truck (Globe) mix and pump in 30 sacks gel mud. Put in plug - mix and pump in 100 sacks cement/370" CC. Shut in at 125 psi.

RECEIVED  
CONSERVATION COMMISSION  
SEP 3 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ace Pipe Pulling Company  
Address Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.  
E. M. Hilton - President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) [Signature]  
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 19 59  
Carmen Reinhardt Leiker  
Carmen Reinhardt Leiker Notary Public.

My commission expires January 26, 1963

PLUGGING  
FILE SEC. 3 121 R 130  
BOOK PAGE 57 LINE 17

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

COPY


15.185.61667.0000

Company- HILTON DRILLING CO., INC.  
Farm- Schaeffer No. 1

SEC. 3 T. 21 R. 13W  
SW NW SW

Total Depth. 3565'  
Comm. 8-15-53 Comp. 8-25-53  
Shot or Treated.  
Contractor. Hilton Drlg. Co., Inc.  
Issued. 4-9-55

County Stafford  
KANSAS



CASING:  
8 5/8" 216' w/225 sx cem.  
5 1/2" 3564' w/100 sx cem.

Elevation. 1898 DF

Production. Pmp. 22 B./30% wtr.

Figures indicate Bottom of Formations.

sand-surface clay	70
sand-shale	125
hrd sand-iron	155
shale-shells	218
gryshale-sand	300
red bed shale-shells	760
Anhydrite	785
shale-shells	1000
shale-shells-salt	1375
lime-shale	1845
lime	2010
shale	2070
lime-shale	2450
shale-shells	2535
lime-shale	2980
lime	3192
lime-shale	3273
lime	3504
lime-shale-conglom- erate	3561
Conglomerate	3561 1/2
Arbuckle	3565
Total Depth	

3286  
1898  
1388

TOPS:  
Heebner 3153  
Brown Lime 3273  
Lansing 3286  
Simpson Shale 3536  
Arbuckle 3562