

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 5 Twp. 21S Rge. XXX13 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NE

Lease Owner Texaco Inc.

Lease Name Newcombe Heirs Well No. 1

Office Address 614 Bitting Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-15-1966

Application for plugging filed 7-14-1966

Application for plugging approved 7-15-1966

Plugging commenced 8-6-1966

Plugging completed 8-15-1966

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Box 248, Pratt, Kansas

Producing formation Dry Hole Depth to top          Bottom          Total Depth of Well 3560 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Dry Hole				8-5/8"	221'	None
				4-1/2"	3542'	3008

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet for each plug set.

Rec 3008' 4-1/2" casing. Hole plugged as follows: 3560-3510 w/sand. Dumped 3 sxs cmt on sd bridge @ 3514;. 3514-surface w/10 sxs gel mud & 75 sxs cmt.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1966  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
M. R. Wilson (employee of owner) or XXXXXXXXXX of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) M. R. Wilson  
614 Bitting Bldg., Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of August, 19 66

My commission expires 10-13-69  
Peggy Sue Jones Notary Public.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Stafford County. Sec. 5 Twp. 21 Rge. 13 (E) (W)<sup>X</sup>  
Location as "NE/CNW%SW%" or footage from lines SE SE NE  
Lease Owner Texaco, Inc.  
Lease Name Newcomb Heirs Well No. 1  
Office Address R. R. #1 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 8-6-66 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 8-15-66 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes  
Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3543 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	221	None
				4 1/2	None	3008

RECEIVED  
AUG 29 1966  
CONSERVATION COMMISSION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back from 3560' to 3510'. Cleaned out cellar. Broke off tubing head - unpacked braden head.

Moved in unit.

Rigged up. Run bailer. Mixed and dumped 3 sacks of cement on sand bridge at 3514'. Rigged up jacks. Shot pipe at 3237'. Working pipe.

Working pipe. Shot pipe at 3104'. Working pipe. Shot pipe at 3005'. Pulling pipe.

Pulling pipe. Tried to set overnight bridge - well filled up with water in bailer before cement could be dumped.

Squeezed well with 10 sacks of gel mud and 75 sacks of bulk cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16 day of August, 19 66

My commission expires May 27, 1969

Notary Public.

DRILLER'S LOG

COMPANY  
CONTRACTOR  
FARM  
LOCATION

Texaco, Inc.  
LEBEN DRILLING, INC.  
NEWCOMBE HEIRS #1  
SE SE NE Sec. 5-21s-13w  
STAFFORD COUNTY, KANSAS  
5-16-66  
5-22-66

COMMENCED  
COMPLETED

0	118	Sand
118	142	Hard Sand
142	222	Shale
222	1275	Red Bed and Sand
1275	1600	Shale and Shells
1600	2090	Lime and Shale
2090	2415	Shale and Lime
2415	2675	Shale and Shells
2675	2978	Shale and Lime
2978	3100	Lime and Shale
3100	3543	Lime
	3543	RTD - Set 4 1/2" Casing

RECEIVED  
STATE CORPORATION COMMISSION

JUL 15 1966

CONSERVATION DIVISION  
Wichita, Kansas

Set 8 5/8" new surface casing @ 221' with 200 sacks 60-40 Posmix 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Newcombe Heirs #1 well, located SE SE NE of Section 5, Township 21 South, Range 13 West, Stafford County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 24th day of May, 1966.

Ulanda Nichols  
Ulanda Nichols

My Commission Expires: April 1, 1967