

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Stafford \_\_\_\_\_ 5 21S 13  
County. Sec. No. T<sup>1</sup>S<sup>1</sup>W<sup>1</sup> Rge. (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from line \_\_\_\_\_  
Gabbert-Jones Drilling Company  
Lease Owner: Newcombe 1  
Lease Name: Box 112, Great Bend, Kansas Well No. \_\_\_\_\_  
Office Address: Dry Hole  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed: 8-3-50 19  
Application for plugging filed: 8-3-50 19  
Application for plugging approved: 8-3-50 19  
Plugging commenced: 8-3-50 19  
Plugging completed: Dry Hole 19  
Reason for abandonment of well or producing formation: \_\_\_\_\_

NORTH


Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well: Mr. C. D. Stough 3587 3621 3621  
Producing formation: \_\_\_\_\_ Depth to top: \_\_\_\_\_ Bottom: \_\_\_\_\_ Total Depth of Well: \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
	Run 230' of 8 5/8"	surface,	cemented w/210	sacks cement		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud from TD to 231'; set wood plug @ 231', cemented with 15 sacks cement on top of wood plug, filled with heavy mud to 30' below cellar, set wood plug @ 30' below cellar, cemented with 10 sacks cement on top of wood plug.

RECEIVED

Conservation Div.

AUG 5 - 1950 8-5-1950

STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Gabbert - Jones Drilling Company  
Address: Box 112, Great Bend, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) C. L. Doherty

(Address)

SUBSCRIBED AND SWORN to before me this 4th day of August, 1950

Arthur L. Fickman  
Notary Public.

My commission expires April 16, 1951



Newcombe #1, Stafford County, Kansas

Commenced - 7-17-50

Completed - 8-2-50

Depth		Formation	Remarks
From	To		
0	150	Sand & Clay	
150	200	Sand	
200	231	Shale & Shells	Run 11 Jts. 8 5/8" surface
<del>231</del>	285	Shale	Cemented w/150 sacks cement
285	800	Blue shale & sand & Red Bed	
800	875	Shale & Shells	
875	1215	Shale & Shells	
1215	1515	Shale, Shells & Salt	
1515	1640	Shale & Shells	
1640	1700	Lime	
1700	1805	Broken Lime	
1805	1985	Sandy Lime & Shale	
1985	2080	Shale	
2080	2195	Lime & Shale	
2195	2300	Lime & Shale	
2300	2320	Shale & Shells	
2320	2435	Shale & Shells	
2435	2600	Shale & Shells	
2600	2700	Shale & Lime	
2700	2785	Broken Lime	
2785	2810	Lime & Shale	
2810	2860	Lime	
2860	2905	Lime	
2905	3000	Lime Broken	
3000	3055	Lime	
3055	3109	Lime	
3109	3145	Lime & Shale	
3145	3240	Lime & Shale	
3240	3310	Lime	
3310	3340	Lime	
3340	3400	Lime	
3400	3460	Lime	
3460	3486	Lime	
3486	3510	Lime	
3510	3555	Lime & Shale	
3555	3582	Cong.	
3582	3603	Cong.	
3603	3621 TD	Cong.	Dry Hole, Plugged.

STATE OF KANSAS )  
 COUNTY OF BARTON ) ss ACKNOWLEDGMENT FOR INDIVIDUAL

*C. L. Gabbert*

Before me the undersigned, a Notary Public, within and for said County and State, on this day of August 3rd, 1950, personally appeared, C. L. GABBERT to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My commission expires April 16, 1951

*Alfred L. Friedman*  
 Notary Public

RECEIVED  
 Conservation Div.  
 AUG 5 - 1950  
 STATE CORPORATION  
 COMMISSION  
 KANSAS

PLUGGING  
 FILE SEC 5-21-13c  
 BOOK PAGE 19 LINE 43