


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

STAFFORD

County, Sec. 3 Twp. 21S Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines. NE NE NW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name GIBSON Well No. 1
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed December 20, 1958 19
Application for plugging filed December 20, 1958 19
Application for plugging approved December 20, 1958 19
Plugging commenced December 20, 1958 19
Plugging completed December 20, 1958 19
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3585 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 210 | cemented |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from Total Depth 3585 to 180 feet - plug and 20 sacks cement - mud to 35 feet - another plug and 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Quaker Drilling Co., Inc.
Address 800 Bitting Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Thomas M. McCaul
800 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December 19 58
Virginia Russell Notary Public.

My commission expires August 10, 1961

RECEIVED
STATE CORPORATION COMMISSION
PLUGGING
FILE SEC. 3 T. 21 R. 13W JAN 3 1959
BOOK PAGE 5 LINE 39

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: December 11, 1958

Contractor: Quaker Drilling Co., Inc.

Completed: December 20, 1958

Gibson No. 1
NE NE NW Sec. 3-21S-13W
Stafford County, Kansas

Elevation: 1888 KB

Production: D. & A.

Casing Record

Set 8 5/8 inch casing at 210 feet with 250 sacks cement

(Figures Indicate the Bottom of the Formations)


| <u>FORMATION</u> | <u>DEPTH</u> | <u>FORMATION TOPS</u> | |
|-----------------------|--------------|-----------------------|------------|
| Surface Soil and Sand | 133 | Heebner | 3147 -1259 |
| Hard Sand | 138 | Brown Lime | 3268 -1380 |
| Sand | 155 | Lansing | 3283 -1395 |
| Blue Shale | 210 | Conglomerate | 3524 -1636 |
| Sand | 280 | Simpson | 3535 -1647 |
| Shale | 345 | Arbuckle | 3557 -1669 |
| Red Bed | 745 | Rotary Total Depth | 3585 -1697 |
| Anhydrite | 765 | | |
| Shale and Shells | 920 | | |
| Shale, Shells, Salt | 1450 | | |
| Shale | 1530 | | |
| Lime and Shale | 1665 | | |
| Sandy Lime and Shale | 1775 | | |
| Lime and Shale | 1915 | | |
| Lime | 2050 | | |
| Sandy Lime and Shale | 2250 | | |
| Lime and Shale | 3000 | | |
| Lime | 3135 | | |
| Sandy Shale and Lime | 3230 | | |
| Shale | 3268 | | |
| Lime | 3520 | | |
| Shale and Chert | 3535 | | |
| Sandy Shale | 3557 | | |
| Dolomite | 3585 | | |

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NE NE NW of Section 3, Township 21 South, Range 13 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By: 
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me, a Notary Public, this 31st day of December, 1958.


Virginia Mandell, Notary PublicMY COMMISSION EXPIRES:
August 10, 1961RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1959

PLUGGING
FILE SEC 3 T 21 R 13W
BOOK PAGE 5 LINE 31

DIVISION