


15.185.21028.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 35 Twp. 21 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
60' East-- SE NW SW
Lease Owner L. D. Davis
Lease Name Rose Well No. 1
Office Address P. O. Box 324 Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole
Date Well completed April 28 19 80
Application for plugging filed april 28 19 80
Application for plugging approved April 28 19 80
Plugging commenced 5:45 A.M. April 28 19 80
Plugging completed 6:45 A.M. April 28 19 80
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation Depth to top Bottom Total Depth of Well 3642'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

540' W/40 sx. Pozmix
290' W/40 sx. Pozmix
40' W/40 sx. Pozmix W/wood plug
10 Sx. in Rathole

STATE RECEIVED
MAY 5 1980
COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing

STATE CORPORATION COMMISSION
WICHITA, KANSAS
5-5-1980

STATE OF Kansas COUNTY OF Barton, ss.
Don Popp (employee of owner) or (owner operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Popp
Don Popp Holsington, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of April, 19 80

Bessie M. DeWerff
Bessie M. DeWerff Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

DRILLERS WELL LOG

L. D. Drilling, Inc. - Contractor L. D. Davis - Operator

ROSE # 1
60' East of SE-NW-SW
Sec. 35-21-12
Stafford County, Kansas

T.D. 3642
ELEV. 1834 K.B.

COMMENCED: 4-23-80
COMPLETED: 4-28-80

CASING:

8-5/8" set at 283'

CEMENT:

W/250 sx. 50/50 Pozmix, 2% Gel, 3% CC

FORMATION

DEPTH

Sand	0 - 140
Shale & Red Bed	140 - 283
Red Bed	283 - 940
Shale & Shells	940 - 1425
Shale W/Lime	1425 - 1550
Shale	1550 - 1561
Shale & Shells	1561 - 1930
Shale & Lime	1930 - 2525
Shale & Shells	2525 - 2825
Shale & Lime	2825 - 3175
Lime	3175 - 3425
Lime & Shale	3425 - 3642
R.T.D.	3642

TOPS

Heebner	3111	(-1277)
Brn. Lime	3243	(-1409)
Lansing	3265	(-1431)
Shally Cong.	3558	(-1724)
Cherty Cong.	3589	(-1755)
R.T.D.	3642	

AFFIDAVIT

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.

L D Davis
L. D. Davis

Sworn to and subscribed before me this 29th Day of April, 1980.

My appointment expires: 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

Bessie M. DeWerff
Bessie M. DeWerff, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1980
CONSERVATION DIVISION
Wichita, Kansas