



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Owen of Garvey Drlg. Co. Inc. has this  
date requested permission to plug the following described well:

Mr. Owen guarantees payment of the plugging fee.

Operator's full Name: James R. Wright

Complete Address: 6829 Walmer Prairie Village, Ks

Lease Name: Sitner Well No. 1

Location: NW/SW/NE Sec. 35 Twp. 21s Rge. 12 (E)(W) W

County: Stafford Total Depth 3610 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Owen was instructed to plug the well as follows:

296 ft 8 5/8 surface pipe cemented with 250 sacks. Pump  
40 sacks cement to 600 ft. 2nd plug at 250 ft with 25  
sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks  
cement to surface. 2 sacks cement in rat hole. 2 in mouse  
hole.

Pumped by Globe Cementing Co. Great Bend, Ks

Very truly yours,

Conservation Division Agent