



15.185.26648.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1976

CONSERVATION DIVISION
Wichita, Kansas

6-24-1976

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Curtis of Duke Drlg Co. has this

date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: L.D. Davis

Complete Address: Box 324 Great Bend, KS

Lease Name: Krey Well No. 2

Location: SW/NE/NW Sec. 14 Twp. 21s Rge. 13 (E)(W) W

County: Stafford Total Depth 3575 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Curtis was instructed to plug the well as follows:

305 ft 8 5/8 surface cemented with 275 sacks. Pump plug,


35 sacks cement to 250 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 15 sacks cement to surface. 5 sacks cement in

rat hole.

Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,


Conservation Division Agent