


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 35 Twp. 21 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Lee Phillips Oil Company
Lease Name Sittner Well No. 1
Office Address 1532 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed March 5 19 55
Application for plugging filed June 17 19 69
Application for plugging approved June 20 19 69
Plugging commenced June 20 19 69
Plugging completed June 24 19 69
Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3577 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	262'	8 5/8"	262'	none
		0	3598'	5 1/2"	3598'	2574'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3577' to 3547'. Ran 5 sacks of cement from 3547' to 3517'.

Set plug at 260', set 10' rock bridge and dumped 5 sacks of cement from 250' to 235'. Bailed down oil and water. Ran 20 sacks of cement from 235' to 175'. Filled hole with mud to 40', set rockbridge and capped hole with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July 19 69

My commission expires Feb. 10, 1971
George A Meyer Notary Public.

GABBERT-JONES DRILLING COMPANY
WICHITA, KANSAS
DRILLERS WELL LOG

SITTNER #1
SE SE NW, SECTION 35-21-12W
STAFFORD COUNTY, KANSAS
COMMENCED 2-25-55
COMPLETED 3-5-55

DEPTH		FORMATION	REMARKS
FROM	TO		
0	160	SAND & SHALE	
160	262	SHALE & SHELLS	RAN 262' OF 8 5/8" CASING CEMENTED @ 262' w/200 SACKS CEMENT.
262	600	SHALE	
600	630	ANHYDRITE	
630	1110	SHALE	
1110	1540	SHALE, SHELLS & SALT	
1540	1770	SHALE & SHELLS	
1770	2360	LIME & SHALE	
2360	2620	SHALE & SHELLS	
2620	3040	SHALE & LIME	
3040	3520	LIME	
3520	3572	SHALE & CHERT	
3572	3577	ARBUCKLE	
3577	TD		RAN 3598' OF 5 1/2" CASING SET 3 FEET OFF BOTTOM w/100 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
JUN 18 1969
CONSERVATION DIVISION
Wichita, Kansas

EXECUTED THIS 8th DAY OF MARCH, 1955

H. F. Jones

STATE OF KANSAS }
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 8th DAY OF March, 1955 PERSONALLY APPEARED H. F. Jones TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES 11-19-58

Ernest E. Hall
NOTARY PUBLIC