

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

STAFFORD

County. Sec. 35 Twp. 21 Rge. (E) 12 (W)

Location as "NE/CNWxSWx" or footage from lines SW SE NW

Lease Owner Ed Adair and Lee Phillips

Lease Name Sittner

Well No. 2

Office Address 1017 E. Second St.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 17, 1955

19

Application for plugging filed May 17, 1955

19

Application for plugging approved May 17, 1955

19

Plugging commenced May 17, 1955

19


Plugging completed May 17, 1955

19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend

Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 3640 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8-5/8	236	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3640 - 236 Fill with Heavy mud
 236 1/3 sack Halls and Halliburton Plug
 20 sax cement thru Drill pipe
 35' 1/3 sack Halls and Halliburton Plug
 10 sax cement to base of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shawver Armour, Inc.
Address 817 Central Building, Wichita

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James Armour (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Armour
817 Central Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of May 19 55

My commission expires May 20, 1955

Rosemary Penrose
Notary Public.

MAY 20 1955
CONSERVATION DIVISION
Wichita, Kansas
5-27-1955

PLUGGING
FILE SEC 35 Twp. 21 R 12W
BOOK PAGE 119 LINE 35

DRILLING LOG

COMPANY: Ed Adair Oil Company
Lee Phillips Oil Co.

Location: SW SE NW
35 21 12
Stafford
County

CONTRACTOR: Shawver-Armour, Inc.

FARM NAME: Sittner #2

Elevation: 1835 KB

COMMENCED: May 9, 1955
COMPLETED: May 17, 1955

CASING RECORD

236' 8-5/8" w/235 sx cem.

FORMATION	FROM	TO	
Sand, Clay, Red Bed	0	236	TOPS
Red Bed, Shale & Shells		1050	
Shale		1190	Heebner 3107
Salt & Shale		1460	Brown Lime 3239
Shale & Shells		1526	Lansing 3260
Shale & Lime		3140	
Shale		3240	
Lime Brown		3340	
Lime		3460	
Lime & Shale		3583	
Conglomerate		3649	RTD

STATE OF KANSAS)
) ss
SEDGWICK COUNTY)

I, James Armour, do hereby certify that the above is a true and correct copy of the log on the above captioned well, as shown on the daily drilling reports.

SHAWVER-ARMOUR, INC.

BY: James Armour
James Armour, Sec'y-Treas.

Subscribed and sworn to before me this 22 day of May 1955.

Rosemary Pearce
Notary Public

My commission expires Mar 30, 1957.

RECEIVED
DIVISION

PLUGGING
SEC 35 21 12W
PAGE 19 LINE 35