

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 35 Twp. 21s Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SW NE

Lease Owner James R. Wright

Lease Name Sittner Well No. 1

Office Address 6829 Walmer, Prairie Village, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 8 1972

Application for plugging filed August 8 1972

Application for plugging approved August 8 1972


Plugging commenced August 8 1972

Plugging completed August 8 1972

Reason for abandonment of well or producing formation No Productible Zone

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. R. Biburstein

Producing formation Depth to top Bottom Total Depth of Well 3610 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	276	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Gunned up pits forming heavy mud. Filled hole with heavy mud, spotted 40 sacks cement at 600 feet. Filled hole with heavy mud, spotted 25 sacks cement @ 250 feet. Filled hole with heavy mud, pushed wooden plug to 40 feet and capped with 10 sacks cement to base of well cellar. Job complete @ 7:30 AM 8-8-72

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address Box 1164, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

Ben E. Unruh (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben E. Unruh

Box 1164, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August, 1972

My commission expires July 8, 1974

Notary Public.

WELL LOG

COMPANY James R. Wright

SEC. 35 T. 21S R. 12W

FARM Sittner NO. 1

LOC. NW SW NE


TOTAL DEPTH 3610'

COUNTY Stafford Co., Kansas

COMM. 7-29-72 COMP. 8-8-72

CONTRACTOR Garvey Drilling Company

CASING 8 5/8" @ 296' w/240 sacks



ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 296' Sand
- 873' Red Bed & Shale
- 1500' Shale & Shells
- 3348' Lime & Shale
- 3490' Lime
- 3560' Lime & Chert
- 3587' Chert, Lime, Shale & Arbuckle
- 3610' Lime & Chert

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1972
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
 County of Barton } ss

I, Eunice I. McEachern of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Sittner No. 1 well.

Eunice I. McEachern

Subscribed and sworn to before me this 15th day of August 19 72

My Commission Expires: July 8, 1974

George A. Morris
 NOTARY PUBLIC