

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 23 Twp. 21 Rge. 12W E/W
Location as "NE/CNW/SW" or footage from lines
C W/2 NW


Lease Owner J. L. Chew, Inc.
Lease Name MAXWELL Well No. 2
Office Address Box 526, Lyons, KS 67554
Character of Well (Completed as Oil, Gas or Dry Hole) Dry hole

Date Well completed 4/14/1981
Application for plugging filed 4/14/1981
Application for plugging approved 4/14/1981
Plugging commenced 4/14/1981
Plugging completed 4/14/1981

Reason for abandonment of well or producing formation Dry hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3661
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	298'	8-5/8"	298'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

50 sks @ 480'
30 sks @ 300'
10 sks @ 40'
10 sks rathole
50/50 pox. 3% c.c.
plug down 4:50 am
4/14/81

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Company
P.O. Box 1389, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.
Greg Davidson (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Greg Davidson
P.O. Box 1389, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 81



Ruth Brack
Notary Public.

My commission expires _____

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1981
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S WELL LOG

DATE COMMENCED: 04/09/81
 DATE COMPLETED: 04/14/81

J. L. Chew, Inc.
 MAXWELL No. 2
 C W/2 NW
 Sec. 23, Twp. 21S, Rge. 12W,
 Stafford County, Kansas

ELEVATION: 1852' G.L.
 1857' K.B.

FORMATION DATA:

3121 - 3257'	Shale	Heebner	3121'
3257 - 3267'	Lime, shale	Brown Lime	3257'
3267 - 3511'	Lime	Lansing	3267'
3511 - 3631'	Shale, lime, chert, sand	Conglomerate	3511'
3631 - 3661'	Chert	Viola	3631'
3661'	RTD	RTD	3661'

SURFACE DATA:

Ran 7 jts. new 20# 8-5/8" casing; tally: 291'; Set @ 298' w/ 300 sks 60/40 poz. 2% gel, 3% c.c., plug down @ 7.15 PM, 4/9/81
 By Howco.

PLUGGING DATA:

50 sks @ 480'
 30 sks @ 300'
 10 sks @ 40'
 10 sks rathole
 50/50 poz. 3% c.c. plug down 4:50 AM, 4/14/81
 By

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

Greg Davidson , of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Greg Davidson

Subscribed and Sworn to before me this 23rd day of April, 1981.



Ruth Brack
 RECEIVED
 Notary Public
 STATE OF KANSAS
 JUN 10 1981
 CONSERVATION DIVISION
 Wichita, Kansas

DRILLER'S WELL LOG

DATE COMMENCED: 04/09/81
 DATE COMPLETED: 04/14/81

J. L. Chew, Inc.
 MAXWELL No. 2
 C W/2 NW
 Sec. 23, Twp. 21S, Rge. 12W,
 Stafford County, Kansas

ELEVATION: 1852' G.L.
 1857' K.B.

FORMATION DATA:

3121 - 3257'	Shale	Heebner	3121'
3257 - 3267'	Lime, shale	Brown Lime	3257'
3267 - 3511'	Lime	Lansing	3267'
3511 - 3631'	Shale, lime, chert, sand	Conglomerate	3511'
3631 - 3661'	Chert	Viola	3631'
3661'	RTD	RTD	3661'

SURFACE DATA:

Ran 7 jts. new 20# 8-5/8" casing; tally: 291'; Set @ 298' w/ 300 sks 60/40 poz. 2% gel, 3% c.c., plug down @ 7.15 PM, 4/9/81 By Howco.

PLUGGING DATA:

50 sks @ 480'
 30 sks @ 300'
 10 sks @ 40'
 10 sks rathole
 50/50 poz. 3% c.c. plug down 4:50 AM, 4/14/81 By STATE COMMISSIONER

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

MAY - 6 1981
 CONSERVATION DIVISION
 Wichita, Kansas

Greg Davidson , of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Greg Davidson

Subscribed and Sworn to before me this 23rd day of April, 1981.



Ruth Brack
 Notary Public