

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Durby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-22,875.0000

LEASE NAME MONTE

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 23 TWP. 21S RGE. 12 (X) or (W)

COUNTY Stafford

LEASE OPERATOR L. D. Drilling, Inc.

ADDRESS R.R. 1 Box 183 B Great Bend, Kansas 67530

PHONE#(316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 9-29-92

Plugging Commenced 9-29-92

Plugging Completed 9-29-92

The plugging proposal was approved on September 29, 1992 (date)

by Glen Barlow - Duane Rankin on location (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3625'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
surface		0	313'	8 5/8"	313'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50 sx. @ 640', 50 sx. @ 340', 10 sx. @ 40', 15 sx. in rat hole

Total 125 sx. 60/40 Pozmix, 6% Gel & 1/2# flosill

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L.D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L.D. Drilling, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.

Greg Davidson

(Employee of Operator) or (State Corporation Commission)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Greg Davidson


(Address) R.R. 1 Box 183 B Great Bend, Kansas 67530

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 15 1992
 CONSERVATION DIVISION
 Wichita, Kansas KS
 67530

SUBSCRIBED AND SWORN TO before me this 8th day of October, 19 92

Bessie M. DeWerff
 Notary Public
 Bessie M. DeWerff

My Commission Expires: 5-20-93



COMMENCED: 9-23-92
COMPLETED: 9-29-92

DRILLER'S WELL LOG

0 - 314 Sand & Red beds
314 - 350 Sand
350 - 965 Red beds & shales
965 - 2975 Lime & Shale
2975 - 3165 Lime
3165 - 3335 Douglas Shale & Lime
3335 - 3435 Lime & Shale
3435 - 3440 Lime
3440 - 3530 Lime & Chert
3530 - 3625 Lime
3625 RTD

L. D. DRILLING, INC.
MONTE #1
NE NE NE
SEC. 23-T21S-R12W
Stafford County, KS.

ELEVATION: 1832 GR 1837 KB

FORMATION DATA: (sample)

Anhy. 614 (+1223)
Base Anhy. 637 (+1200)
Heebner 3092 (-1255)
Brown Lime 3219 (-1382)
Lans. K/C 3247 (-1410)
Base K/C 3468 (-1627)
Viola 3505 (-1668)
Simpson 3539 (-1702)
Arbuckle 3592 (-1755)
RTD 3625 (-1788)

SURFACE CASING:


8 5/8" set @ 313' W/225 sx.
50/50 Pozmix, 2% Gel, 3% CC

A F F I D A V I T

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.


Greg Davidson

Subscribed and sworn to before me this 8th day of October 1992.




Bessie M. DeWerff Notary Public

My Commission Expires: 5-20-93

RECEIVED
STATE CORPORATION COMMISSION

OCT 15 1992

CONSERVATION DIVISION
Wichita, Kansas