


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

STAFFORD County. Sec. 23 Twp. 21S Rge. 12W (E) \_\_\_\_\_ (W)  
Location as "NE/CNW%SW%" or footage from lines SE NE NE  
Lease Owner HELMERICH & PAYNE, INC.  
Lease Name THUL MAXWELL Well No. 1  
Office Address First National Bank Building, Tulsa 3, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 4, 1961  
Application for plugging filed April 4, 1961  
Application for plugging approved April 4, 1961  
Plugging commenced April 5, 1961  
Plugging completed April 5, 1961  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3650 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Red Bed	Surface Csg.	-0-	268'	8-5/8"	268'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGED: Filled hole with mud 3650' up to 240'; set bridge using 1/3 sk. hulls, plug, 20 sx. cement through drill pipe. Filled hole to 35' with mud, 10 sx. cement to cellar zero.

Job completed: 1 a.m. - 4-5-61.

RECEIVED  
STATE CORPORATION COMMISSION

APR 6 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor SIERRA PETROLEUM CO., INC.  
Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
C. T. HONAKER, DRILLING SUPT. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DELG. SUPT.

Box 232, Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of April, 1961

My commission expires 10-17-63

Geroy Sisk  
Notary Public.



HELMERICH & PAYNE, INC. - Operator

SIERRA PETRO. CO., INC. - Contr.

THUL MAXWELL #1  
SE NE NE  
Sec. 23-21S-12W  
Stafford County, Kansas

T. D.: 3650'  
Elev.: 1847' K.B.

Commenced: 3-25-61  
Completed: 4-4-61

Casing:

Cement:

8-5/8" Set at 268'

with 250 sx. cement

FORMATION

Sand	240'
Red Bed	630'
Anhydrite	647'
Shells, Shale & Salt	1110'
Shale & Shells	1515'
Lime & Shale	2735'
Lime	3609'
Conglomerate & Arbuckle	3650'

TOPS:

Anhydrite	630'
Topeka	2820'
Heebner	3110'
Toronto	3129'
Brown Lime	3236'
Lansing K. C.	3254'
Base K. C.	3487'
Conglomerate	3504'
Simpson Shale	3566'
Arbuckle	3612'

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true  
and correct to the best of my knowledge.

C. T. Harker

Subscribed and sworn to before me this 5th day of April

1961.

Henry Ditz  
Notary Public

My commission expires: 10-17-63

RECEIVED  
STATE CORPORATION COMMISSION  
APR 6 1961  
CONSERVATION DIVISION  
Wichita, Kansas