

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County. Sec. 14 Twp. 21 Rge. 13 (X) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner Petroleum, Inc.

Lease Name Krey Well No. 1

Office Address 305 East Third, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 9, 19 52

Application for plugging filed November 9, 19 52

Application for plugging approved November 9, 19 52

Plugging commenced November 9, 19 52

Plugging completed November 9, 19 52

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3605 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 210' and set wooden plug at 210'. Cemented and displaced 20 sacks cement through drill pipe onto plug at 210'. Mudded up to 35' and set second wooden plug. Filled hole to bottom of well cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1952

CONSERVATION DIVISION (If additional description is necessary, use BACK of this sheet)
Wichita, Kansas

Name of Plugging Contractor Garvey Drilling Company

Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

W. W. Fisher (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Fisher

305 East Third, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November, 19 52

Charlotte Heisman (Signature)

Notary Public.

My commission expires October 13, 1954

PLUGGING
FILE SEC 14 T 21 R 13
BOOK PAGE 57 LINE 40

DRILLER'S LOG KREY NO. 1

Petroleum, Inc., Operator

Section 14, Twp. 21S, Rge. 13W

Garvey Drilling Company, Contractor

Location: NE NE NW

Drilling Commenced: October 31, 1952

County: Stafford County, Kansas

Drilling Completed: November 9, 1952

R.T.D.: 3605'

Casing Record: 8 5/8" @ 215' w/175 sax

Production: D & A

Figures below indicate bottom of formation:

30	Clay
41	Sand
170	Sand & Clay
215	Shale
260	Shale & Shells
716	Red Bed
744	Anhydrite
1560	Shale & Shells
3041	Lime & Shale
3167	Lime
3260	Lime & Shale
3543	Lime
3605	Lime & Shale

Tops:

Heebner:	3141 (-1270)
Brown Lime:	3268 (-1397)
Lansing:	3286 (-1415)
Simpson:	3544 (-1673)
Arbuckle:	3599 (-1728)

3605' R.T.D.

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1952

CONSERVATION DIVISION
Topeka, Kansas

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W.W. Fish

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, this 14th day of November, 1952.

Charlotte Hudson
Notary Public

My commission expires: October 13, 1954.

PLUGGING
FILE SEC 14 T 21 R 13W
BOOK PAGE 57 LINE 40