

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-1

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

			X

Locate well correctly on above
Section Plat

Stafford County, Sec. 14, Twp. ~~25~~²¹, Rge. 13 (E) W (W)
 Location as "NE/CNW/SE" or footage from lines NE SE SE
 Lease Owner Aspen Drilling Co.
 Lessee Name Hall Well No. #1
 Office Address P. O. Box 783 ; Great Bend, Ks. 67530
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed _____ 19____
 Application for plugging filed June 19 74
 Application for plugging approved June 19 74
 Plugging commenced June 25 19 74
 Plugging completed July 8 19 74
 Reason for abandonment of well or producing formation _____
 If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250	None
				5 1/2"	3716	2700

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

June 26, 1974 Plugged off bottom. Dumped sand to 3300'. Mixed and dumped 5 sacks cement.
 July 8, 1974 Plugged off top. Sun Oil Well Cementing Co. mixed and pumped down 8 5/8" surface casing; 3 sx of hulls, 10 sx of gel and 100 sx of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1974
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor, RUSS CASING PULLING, INC.
 Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.
 John H. Volosin (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Volosin
 P. O. Box 783, Great Bend, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 16th day of July, 19 74

My commission expires April 18, 1976
 Theora Holleman Notary Public.

DRILLERS LOG

COMPANY: Aspen Drilling Co.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Hall #1
 LOCATION: NE SE SE Sec.14-T21S-R13W
 Stafford County, Kansas
 ELEVATION: 1869 KB
 SURFACE CASING: 6 jts. (242') 8 5/8"
 OIL STRING: 119 jts. (3714') 5 1/2"
 COMMENCED: October 23, 1968
 COMPLETED: October 31, 1968
 ROTARY TOTAL DEPTH: 3718'

<u>FORMATION</u>	<u>DEPTH</u>	
Sand	225	Ran 6 jts.(242') 8 5/8" casing set at 250', cemented with 250 sacks. Cement circulated.
Shale	255	
Red Bed	360	
Shale	709	DST #1 3318-3345
Anhydrite	735	DST #2 3350-3368
Shale-Shells	1065	DST #3 3400-3427
Shale	1590	DST #4 3510-3608
Shale-Lime	1820	DST #5 3609-3629
Lime-Shale	2035	
Shale-Lime	2875	Ran electric log
Lime	3608	
Arbuckle	3718	Ran 119 jts.(3714') 5 1/2" set at 3716', cemented with 150 sacks.

ELECTRIC LOG TOPS

Anhydrite	718
Base Anhydrite	739
Heebner	3150
Toronto	3169
Douglas	3183
Brown Lime	3275
Lansing	3515
Base K. C.	3535
Conglomerate	3557
Simpson	3606
Arbuckle	3606
Log T. D.	3717

RECEIVED
 STATE CORPORATION COMMISSION


JUN 27 1964
 CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

State of Kansas)
) ss:
 County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle



Subscribed and sworn to before me: this 6th day of November, 1968.

Theora Holleman
 Theora Holleman, Notary Public

My commission expires: April 18, 1972