


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 27 Twp. 21 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner Dafga, Inc.
Lease Name Wilson Well No. E-1
Office Address Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 12-7-67 19____
Application for plugging approved 12-8-67 19____
Plugging commenced 1-27-68 19____
Plugging completed 2-10-68 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3659 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	220	None
				5 1/2	None	2125

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Rigged up. Dug out cellar. Plugged off bottom. Sanded to 3475' with 5 sacks of cement. Rigged up jacks. Pulled 20" tension.

Working pipe. Shot pipe at 2900'. Circulating. Spotted 65 bbl of oil.

Working pipe. Pushed plug to bottom.

Shot pipe at 2615' - 2312' and 2153'. Pulling pipe.

Squeezed well with 10 sacks of mud and 80 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss. J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of February, 19 68

My commission expires May 27, 1969
Glenn O. ... Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY.
508 East Murdock, Wichita, Kansas.


15. 185-00884-0000
COPY

Company- PETROLEUM, INC.
Farm- Wilson "E" No. 1

SEC. 27 T. 21 R. 12W
NE SW NE

Total Depth. 3655'
Comm. 9-17-54 Comp. 9-27-54
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 2-19-55

County Stafford
KANSAS



CASING:
8 5/8" 220' cem w/200, sx

Elevation. 1846' RB

Production. Dry

Figures Indicate Bottom of Formations.

sand	190
red rock	220
red bed	360
sand & shale	500
shale & shells	625
anhydrite	655
shale & shells	1490
lime & shale	2855
lime	2915
lime & shale	3250
lime	3524
lime & shale	3590
lime	3655
Total Depth	
Tops:	
Hebner	3118
Toronto	3135
Douglas	3148
Brown Lime	3250
Lansing	3263
Viola Chert	3524
Simpson	3553
Arbuckle	3603

RECEIVED
CORPORATION COMMISSION

DEC 13 1957

CONSERVATION DIVISION
Wichita, Kansas