

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-185-20797.0001

API NUMBER 15-185-20797001

LEASE NAME Siefkes OWWD

WELL NUMBER 3

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 27 TWP. 21 RGE. 12 (E) or (W)

COUNTY Stafford

Date Well Completed 2-13-78

Plugging Commenced 12-16-96

Plugging Completed 12-16-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Coes. Div.  
office within 30 days.

LEASE OPERATOR L.D. Drilling, Inc.

ADDRESS R.R. 1, Box 183-B, Great Bend, Kansas 67530

PHONE (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well SWD

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-16-96 (date)

by Richard Lacey (XCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 3252 Bottom 3654 T.O. 3695

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	285'	0
	Production			5 1/2"	3694	1709

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, - from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set  
Bottom plug; sanded off to 3250'. Allied cemented 1st- 300 lbs. hulls 10 sks gel 50 cement 10 sks gel, 100 lbs. hulls, released 8 5/8" plug; mixed 125 sks cement shut in.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L.D. Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Joseph J. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Joseph J. Strube


(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 96

Karlynn K. Beck  
Notary Public

My Commission Expires: 09-28-98

USE ONLY ONE SIDE OF EACH FORM



Corrected copy as to correct RTD 3646

DRILLERS' WELL LOG

*Dys*

DATE COMMENCED: February 7, 1978  
DATE COMPLETED: February 13, 1978

L. D. Davis  
SIEFKES #1  
SE NE NE Sec. 27-T21-R12W  
Stafford County, Ks.

0 -	20'	Surface Soil & Sand
20 -	198'	Sand & Clay
198 -	285'	Red Bed
285 -	616'	Shale & Red Bed
616 -	636'	Anhydrite
636 -	1390'	Shale & Red Bed
1390 -	1758'	Shale & Lime Streaks
1758 -	2817'	Lime & Shale
2817 -	3119'	Lime
3119 -	3123'	Shale
3123 -	3151'	Lime
3151 -	3253'	Shale
3253 -	3272'	Lime & Shale
3272 -	3497'	Lime
3497 -	3515'	Lime & Shale
3515 -	3541'	Shale, Lime, Chert
3541 -	3581'	Chert, Lime
3581 -	3600'	Shale, Lime
3600	3646'	RTD

ELEVATION: 1846 K.B.

FORMATION DATA

ANHYDRITE	616
TOPEKA	2827
HEEBNER	3119
TORONTO	3139
DOUGLAS	3151
BR. LIME	3253
KANSAS CITY	3272
BASE K.C.	3497
CONGLOMERATE	3515
VIOLA	3541
SIMPSON	3581
ARBUCKLE	3600
RTD	3646

RECEIVED  
STATE COOPERATION COMMISSION  
FEB 28 1978  
CONSERVATION DIVISION  
Wichita, Kansas

SURFACE PIPE: Set 285' of  
8-5/8", 28# pipe with 225 sacks  
cement, 50/50 pozmix (2% Gel, 3% Ch.c)

A F F I D A V I T

State of Kansas } ss  
County of Barton }

Leonard Williamson, of lawful age does swear and state that the facts  
and statements herein contained are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 17 day of February 1978.

My Commission Expires: 4-11-78

*W. H. Nagus*  
Notary Public