


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 27 Twp. 21 Rge. 12 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
SE NE NE
Lease Owner L. D. Davis
Lease Name Siefkes Well No. 1
Office Address Box 324 - Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole) x



Locate well correctly on above
Section Plot

Date Well completed February 13 1978
Application for plugging filed Feb. 13 1978
Application for plugging approved " 1978
Plugging commenced Feb. 15 (due to snowstorm) 1978
Plugging completed Feb. 15 1978
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3646
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of heavy mud; bottom plug at 540' w/40 sacks cement thru drill pipe.
Middle plug at 285' w/35 sacks cement thru drill pipe.
Top plug 2 40' w/ $\frac{1}{2}$ sk. hulls & 12 sacks cement.
2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc

STATE OF Kansas COUNTY OF Barton, ss.
Leonard Williamson (employee of owner) or (~~XXXXXXXXXXXX~~)
of the above-described well, being first duly sworn on oath, says; That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson
Box 823 - Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of February, 19 78

Dorothy M. Hague
Notary Public.

My commission expires April 11, 1978

15.185.20797.0000
DUP

DRILLERS' WELL LOG

DATE COMMENCED: February 7, 1978
DATE COMPLETED: February 13, 1978

L. D. Davis
SIEFKES #1
SE NE NE Sec. 27-T21-R12W
Stafford County, Ks.

0	=	20'	Surface Soil & Sand
20	-	198'	Sand & Clay
198	-	285'	Red Bed
285	-	616'	Shale & Red Bed
616	-	636'	Anhydrite
636	-	1390'	Shale & Red Bed
1390	-	1758'	Shale & Lime Streaks
1758	-	2817'	Lime & Shale
2817	-	3119'	Lime
3119	-	3123'	Shale
3123	-	3151'	Lime
3151	-	3253'	Shale
3253	-	3272'	Lime & Shale
3272	-	3497'	Lime
3497	-	3515'	Lime & Shale
3515	-	3541'	Shale, Lime, Chert
3541	-	3581'	Chert, Lime
3581	-	3600'	Shale, Lime
3600	-	3646'	RTD

ELEVATION: 1846 K.B.

FORMATION DATA

ANHYDRITE	616
TOPEKA	2827
HEEBNER	3119
TORONTO	3139
DOUGLAS	3151
BR. LIME	3253
KANSAS CITY	3272
BASE K.C.	3497
CONGLOMERATE	3515
VIOLA	3541
SIMPSON	3581
ARBUCKLE	3600
RTD	3646

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1978
CONSERVATION DIVISION
Wichita, Kansas

SURFACE PIPE: Set 285' of
8-5/8", 28# pipe with 225 sacks
cement, 50/50 pozmix (2% Gel, 3% Ch. cl.)

A F F I D A V I T

State of Kansas) ss
County of Barton)

Leonard Williamson, of lawful age does swear and state that the facts
and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 17 day of February 1978.

My Commission Expires: 4-11-78

Anthony M. Hague
Notary Public