


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 27 Twp. 21 Rge. 12 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE NE  
Lease Owner Duke Drilling Company  
Lease Name Wilson Well No. 1  
Office Address Box 123, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed 3/16 1956  
Application for plugging filed 3/16 1956  
Application for plugging approved 3/16 1956  
Plugging commenced 3/16 1956  
Plugging completed 3/16 1956  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Russell Brunderidge  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3640 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION    | CONTENT | FROM | TO  | SIZE  | PUT IN | PULLED OUT |
|--------------|---------|------|-----|-------|--------|------------|
| Sand         |         | 0    | 185 |       |        |            |
| Shale & clay |         | 185  | 250 |       |        |            |
| Red bed      |         | 250  | 256 | 8-5/8 | 256'   | none       |
|              |         |      |     |       |        |            |
|              |         |      |     |       |        |            |
|              |         |      |     |       |        |            |
|              |         |      |     |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 240'. Bottom plug at 240' with 1/3 sack hulls, 20 sacks wet cement thru drill pipe. Heavy mud to 35'. Top plug at 35' with 1/3 sack hulls. Filled hole with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Company  
Address P. O. Box 123, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.  
Clair Stimson (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clair Stimson  
THE DUKE DRILLING COMPANY  
(Address)

SUBSCRIBED AND SWORN TO before me this 22<sup>nd</sup> day of March, 1956

My commission expires July 29, 1957

Notary Public.



3-25-56

WELL LOG

Date started: 3/7/56  
Date Completed: 3/17/56

Wilson #1  
SE SE NE Sec. 27-21-12  
Stafford County

|               |               |
|---------------|---------------|
| Elevation     | 1839 K.B.     |
| Anhydrite     | 621'          |
| Heebner       | 3124' (-1285) |
| Brown lime    | 3257' (-1418) |
| Kansas City   | 3277' (-1438) |
| Shaley Congl. | 3510' (-1671) |
| Cherty Congl. | 3545' (-1706) |
| R.T.D.        | 3640' (-1801) |

|       |   |       |                  |
|-------|---|-------|------------------|
| 0     | - | 185'  | Sand             |
| 185   | - | 250'  | Shale and clay   |
| 250   | - | 256'  | Red bed          |
| 256   | - | 621'  | Red bed          |
| 621   | - | 638'  | Anhydrite        |
| 638   | - | 1120' | Shale & shells   |
| 1120  | - | 1160' | Shale and shells |
| 1160  | - | 1285' | Salt and shale   |
| 1285  | - | 1475' | Shale and shells |
| 1475  | - | 1635' | Shale and shells |
| 1635  | - | 1890' | Lime and shale   |
| 1890  | - | 2215' | Lime and shale   |
| 2215  | - | 2675' | Lime and shale   |
| 2675  | - | 3015' | Lime             |
| 3015  | - | 3124' | Lime             |
| 3124  | - | 3230' | Heebner          |
| 3230  | - | 3257' | Lime             |
| 3257  | - | 3277' | Brown lime       |
| 3277  | - | 3300' | Kansas City      |
| 3300  | - | 3385' | Lime             |
| 3385  | - | 3510' | Lime             |
| 3510  | - | 3640' | Conglomerate     |
| 3640' |   |       | R.T.D.           |

AFFIDAVIT

State of Kansas..... County of Barton.

I, Clair E. Stinson, employee of the owner, do swear that the statements and matter herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

BY: Clair E. Stinson  
Clair E. Stinson

Subscribed and sworn before me this 20th day of March, 1956

Jane Swamy  
NOTARY PUBLIC

My commission expires: July 29, 1957

**PLUGGING**  
 SEC 27 T 21 R 12W  
 BOOK PAGE 46 LINE 31

STAFFORD COUNTY  
 WINDIC, ILLINOIS