

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County, Sec. 27 Twp. 21 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Dafra, Inc.  
Lease Name Wilson Well No. 1  
Office Address Victoria, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 12-7-67 19\_\_\_\_  
Application for plugging approved 12-8-67 19\_\_\_\_  
Plugging commenced 1-11-68 19\_\_\_\_  
Plugging completed 1-26-68 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3685 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	307	None
				4 1/2	None	2019

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Ripped up jacks. Pulled 14" tension. Shot pipe at 3180'.  
Spotted 43 bbl of oil.

Working pipe. Shot pipe at 2875'. Circulating water.

Shot pipe at 2500'. Working pipe. Shot pipe at 2000'. Working pipe.

Pulling pipe.

Pushed plug to 280'. Set 10' rock bridge. Dumped 7 sacks of cement.  
Dumped 10 sacks of cement. Mudded to 40'. Set 10' rock bridge. Capped well with 10 sacks.

1-31-68  
RECEIVED  
STATE CORPORATION COMMISSION  
JAN 31 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of January, 19 68

My commission expires May 27, 1969

Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15-185-12468-0000


COPY

Company - ANSCHUTZ DRILLING CO., INC.  
Farm - Wilson No. 1

SEC. 27 T. 21 R. 12W  
NE NE NE

Total Depth. 3685  
Comm. 8-15-50 Comp. 8-25-50  
Shot or Treated.  
Contractor.  
Issued. 9-16-50

County. Stafford  
KANSAS



CASING:  
8 5/8" 309' cem w/225 sx.

Elevation. 1845

Production. Dry

Figures Indicate Bottom of Formations.

surface clay, sand	40
sand	205
red bed, sand strks	333
red bed, shells	605
anhyd.	630
shale, shells	960
shale, shells, salt	1330
shale, shells	1500
lime	1720
lime brkn, shale	1790
lime sdy	1880
lime brkn, shale	1945
lime, shale	2070
shale, shells	2245
lime	2310
lime shale	2540
shale, shells	2770
lime, shale	2995
lime	3114
lime, shale	3180
shale, shells	3275
lime	3490
lime shale	3530
lime, chert, shale	3572
lime, shale	3598
cong.	3600
arbuckle, shale	3637
lime, shale	3650
lime	3685
Total depth	

Tops:	
Heebner	3116
Br. lime	3249
Kansas City	3254
Cong.	3506
Viola	3536
Simpson shale	3561
Reworked arbuckle	3600
Sol. Arbuckle	3655

RECEIVED  
STATE CONSERVATION COMMISSION

DEC 13 1961

CONSERVATION DIVISION  
Wichita, Kansas